



US Army Corps
of Engineers

MISCELLANEOUS PAPER GL-91-4

(2)

CONDITION SURVEY AND PAVER IMPLEMENTATION DAVIS-MONTHAN AIR FORCE BASE, ARIZONA

by

Thomas B. Rosser III

Geotechnical Laboratory

DEPARTMENT OF THE ARMY

Waterways Experiment Station, Corps of Engineers
3909 Halls Ferry Road, Vicksburg, Mississippi 39180-6199

AD-A233 396

PAVEMENT CONDITION INDEX (PCI)	PAVEMENT CONDITION RATING
100	EXCELLENT
85	VERY GOOD
70	GOOD
55	FAIR
40	POOR
25	VERY POOR
10	FAILED
0	



DTIC
ELECTE
APR 11 1991
S C D



February 1991

Final Report

Approved For Public Release; Distribution Unlimited

DTIC COPY

DTIC FILE COPY



Prepared for DEPARTMENT OF THE AIR FORCE
Langley Air Force Base, Virginia 23665-5001

Under MIPR No. N589-119

91 4 10 113

Destroy this report when no longer needed. Do not return
it to the originator.

The findings in this report are not to be construed as an official
Department of the Army position unless so designated
by other authorized documents.

The contents of this report are not to be used for
advertising, publication, or promotional purposes
Citation of trade names does not constitute an
official endorsement or approval of the use of
such commercial products.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE February 1991	3. REPORT TYPE AND DATES COVERED Final report		
4. TITLE AND SUBTITLE Condition Survey and Paver Implementation, Davis-Monthan Air Force Base, Arizona		5. FUNDING NUMBERS MIPR No. N589-119		
6. AUTHOR(S) Thomas B. Rosser III				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) USAE Waterways Experiment Station, Geotechnical Laboratory, 3909 Halls Ferry Road, Vicksburg, MS 39180-6199		8. PERFORMING ORGANIZATION REPORT NUMBER Miscellaneous Paper GL-91-4		
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) US Air Force , Langley Air Force Base, VA 23665-5001		10. SPONSORING / MONITORING AGENCY REPORT NUMBER		
11. SUPPLEMENTARY NOTES Available from National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161.				
12a. DISTRIBUTION / AVAILABILITY STATEMENT Approved for public release; distribution unlimited		12b. DISTRIBUTION CODE		
13. ABSTRACT (Maximum 200 words) A pavement condition survey was performed at Davis-Monthan Air Force Base, Arizona, in September 1989 for the purpose of determining the pavement condition index of the airfield features and for performing the initial implementation of the PAVER pavement management system.				
14. SUBJECT TERMS Airfield pavement Davis-Monthan Air Force Base Pavement condition		Pavement condition index PAVER PAVER implementation		15. NUMBER OF PAGES 186
17. SECURITY CLASSIFICATION OF REPORT Unclassified		18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified		16. PRICE CODE
		19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified		20. LIMITATION OF ABSTRACT

PREFACE

The condition survey described in this report was requested by Military Interdepartmental Purchase Request (MIPR) No. N589-119 dated 7 April 1989 from the Headquarters TAC/DEPF, Langley Air Force Base, VA, to the US Army Engineer Waterways Experiment Station (WES), Vicksburg, MS.

The condition survey at Davis-Monthan Air Force Base was performed by a WES condition survey team during the period 1 to 7 September 1989. The team consisted of Messrs. T. B. Rosser III, D. D. Mathews, R. T. Graham, and J. Duncan, Pavement Systems Division (PSD), Geotechnical Laboratory (GL). This report was prepared by Mr. Rosser under the supervision of Messrs. J. W. Hall, Chief, Systems Analysis Branch, and H. H. Ulery, Jr., Chief, PSD. The work was under the general supervision of Dr. W. F. Marcuson III, Chief, GL, WES.

COL Larry B. Fulton, EN, was the Commander and Director during the preparation and publication of this report. Dr. Robert W. Whalin was the Technical Director.



Accession For	
DTIC 20001	
DTIC 7-1	
Unannounced	
Justified	
By	
Distribution	
Availability	
Date	
Dist	Special
A-1	

CONTENTS

	<u>Page</u>
PREFACE.....	1
CONVERSION FACTORS, NON-SI TO SI (METRIC)	
UNITS OF MEASUREMENT.....	3
PART I: INTRODUCTION.....	4
Background.....	4
Objective and Scope.....	4
PART II: PAVEMENT CONDITION SURVEY.....	5
Introduction.....	5
Pavement Definition and Identification.....	5
Pavement Inspection.....	7
PART III: PAVER DATA BASE IMPLEMENTATION.....	9
Introduction.....	9
Data Entry.....	9
System Sign-On.....	10
Data Upload and Data Base Update.....	10
Report Generation and Data Analysis.....	11
FIGURES 1-27	
PHOTOS 1-26	
APPENDIX A: DATA REPORTS AND ANALYSIS PROGRAMS.....	A1

CONVERSION FACTORS, NON-SI TO SI (METRIC)
UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI
(metric) units as follows:

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
feet	0.3048	metres
inches	2.54	centimetres
square feet	0.09290304	square metres
square yards	0.8361274	square metres

CONDITION SURVEY AND PAVER IMPLEMENTATION
DAVIS-MONTHAN AIR FORCE BASE, ARIZONA

PART I: INTRODUCTION

Background

1. This report describes the condition survey and initial implementation of a pavement management system using the PAVER system of the airfield pavements at Davis-Monthan Air Force Base (AFB), AZ. The implementation was performed to provide base engineers with the initial data base required for making pavement management decisions concerning costs and maintenance requirements. The condition survey was performed by the US Army Engineer Waterways Experiment Station during the period 1 to 7 September 1989.

Objective and Scope

2. The overall objective of this project was to determine the pavement condition of the airfield pavements at Davis-Monthan AFB and to input the information into a PAVER data base to provide the base engineers with a permanent data base to use for future pavement management decisions. The objective was accomplished by:

- a. Performing a condition survey of the pavements in accordance with AFR 93-5.*
- b. Inputting the pavement network and condition survey information into PAVER to calculate a pavement condition index (PCI) of each of the pavement features.
- c. Completing the data base implementation by compiling pavement construction data and inputting the information into the PAVER data base.
- d. Providing detail drawings of the pavement features to ensure that future condition surveys will be performed at the same locations as the one performed for this report.

* Headquarters, Department of the Air Force. 1981 (May). "Airfield Pavement Evaluation Program," Air Force Regulation AFR 93-5, Washington, DC.

PART II: PAVEMENT CONDITION SURVEY

Introduction

3. The information obtained in an airfield pavement condition survey is used to determine the existing surface condition of the airfield pavements. The procedure used in performing a condition survey was developed by the US Army Corps of Engineers and is published as a regulation by the US Air Force. The procedures used are described in detail in AFR 93-5.* Knowledge of these procedures is beneficial in using and understanding this report.

Pavement Definition and Identification

4. The pavement network is divided into three specific units in order to manage the pavement network effectively. The three units of division are the branch, the section, and the sample unit. The method for dividing the pavement network is described in AFR 93-5 and is briefly discussed herein.

5. Airfield pavement branches or features (terminology used by some) are defined by parameters such as the pavement type, construction history, and pavement usage. The branch designations used for Davis-Monthan AFB were established in the 1981 report "Airfield Pavement Condition Survey, Davis-Monthan AFB."** The branch designations, shown in Figure 1, are indicative of pavements subjected to similar traffic with like pavement cross sections.

6. After each pavement branch has been defined, further division of the branch may be required for reasons such as traffic flow. Thus, branches may be further subdivided into sections. For example, a runway branch may be 150 ft† wide, but the majority of the traffic use the middle of the branch. In which case, the center of the branch may be designated as a section of the branch with additional sections defined on either side of the middle section. In like manner, an apron may contain taxi lanes which aircraft use to get to their parking locations. Thus, traffic loadings on the apron may differ

* Headquarters, Department of the Air Force. 1981 (May). "Airfield Pavement Evaluation Program," Air Force Regulation AFR 93-5, Washington, DC.

** Tactical Air Command. 1981 (Jan). "Airfield Pavement Condition Survey, Davis-Monthan AFB", Tucson, AZ.

† A table of factors for converting non-SI units of measurement to SI (metric) units is presented on page 3.

significantly in taxi lanes, as compared with the parking areas, and each may be subdivided into sections of the branch. If a branch (feature) requires no division, for definition purposes it is still considered to contain one section.

7. After the pavement branch and section definition have been completed, each section is divided into sample units. Sample units are conveniently sized areas of pavement within the section on which an inspection can be performed. Ideally, a sample unit on asphaltic concrete (AC) pavement is a 5,000-sq ft area, and on portland cement concrete (PCC) pavement it consists of 20 slabs. A pavement section is divided into sample units for condition survey purposes only. Recognizing that all sample units may not conveniently be 5,000 sq ft or 20 slabs, deviations of 50 percent on either side of these values are allowed for survey purposes.

8. When a section has been divided into sample units, it has been properly prepared for the survey. Inspection of all of the sample units within a section could require considerable amount of time. Therefore, a random sampling method was developed to provide an adequate calculation of the PCI while inspecting only a portion of the sample units in a section. The method, further defined in AFR 93-5, allows for a reduction in the number of sample units surveyed without a significant loss of accuracy in the calculation of the PCI. It should be noted, however, that the inspection of all the sample units may be necessary for estimation of maintenance and repair work.

9. An essential concept in pavement management is determining the deterioration of the pavement surface over time. The PCI is used in the PAVER system to determine this deterioration. Determining the PCI of a pavement branch (feature) at different time intervals requires that the same sample units of the branch be surveyed to get a precise idea of the deterioration rate. Drawings of each of the pavement branch divisions are included in this report with sample unit locations illustrated so that future condition surveys can be conducted at the same locations. The layout of airfield features is shown in Figure 1. Some of the locations of the sample units in the asphalt branches on the runway and taxiway branches were made using stationing. Sample unit locations for the runway, the taxiways, and the apron branches are shown in Figures 2 through 26. The circled numbers indicate the sample units that were surveyed.

Pavement Inspection

10. A condition survey consists of inspecting the pavement surface for various types of distresses, determining the severity of each distress found, and measuring the amount of distress within the sample units inspected. For AC pavement, distress quantities are measured in either linear feet or square feet within the sample unit, and for PCC pavement, quantities are measured by counting the number of slabs affected within the sample unit.

11. The final product of a condition survey is the PCI. The PCI is a value from 0 to 100 (worst to best, respectively) of the surface condition of the pavement. The PCI is obtained by determining a deduct value for the amount of each distress type and the severity found in the inspection, determining a corrected deduct value for the combined effect of various distresses on the pavement condition, and subtracting the corrected deduct value from 100. A pavement with no distress has a PCI of 100. Varying amounts of distress decrease the PCI value to a possible low of 0. Pavement condition ratings (excellent to failed) are assigned to different levels of PCI values; these ratings and their respective PCI value definitions are shown in Figure 27. The PCI of a pavement section is calculated by averaging the PCI's of the sample units inspected. The number of sample units recommended to be inspected in a section is indicated in Figure 4-1 of AFR 93-5 dated July 1989. However, in the survey described herein, a smaller number of sample units were inspected than is recommended by AFR 93-5 because it was directed in WES's statement of work for this condition survey. The number of sample units surveyed were as follows:

Number of Sample Units Surveyed	Number of Sample Units In a Section
1	1-4
2	5-10
3	11-20
10% rounded up	over 40

12. The majority of the pavement branches (features) at Davis-Monthan AFB are rated from good to excellent condition with some features rated from very poor to fair. A listing of the branch names and numbers, an inventory of the pavement types and respective areas by branch, a PCI summary by branch, an inspection schedule report, and individual sample unit inspection results are

shown in Appendix A. An overall layout of the airfield indicating feature location is shown in Figure 1. Figures 2 through 26 show the features and sample units within each feature. Photos 1 through 26 show some of the various distresses that were observed on the airfield pavements.

PART III: PAVER DATA BASE IMPLEMENTATION

Introduction

13. The use of the PAVER system requires knowledge of both computers and the PAVER system itself. This report does not describe the operation of a computer; it does generally describe necessary PAVER procedures. The "PAVER User's Guide"* gives specific details of all the procedures necessary in setting up and using a PAVER data base. The "PAVER User's Guide" should be readily available and used as a reference when performing operations in the PAVER system.

14. The PAVER system consists of five different system functions. Performing each function requires the use of specific programs, files, and procedures. The five functions are data entry, system sign-on, data base update, report generation, and data analysis. Data entry, system sign-on, and data analysis do not directly interact with the PAVER data base, but data base update and report generation require data base interaction.

Data Entry

15. The pavement network data are entered into the PAVER data base in a logical order that defines the features and sections first. The additional information is then entered that allows the user to perform data base related operations such as PCI calculation and report generation. The data must be in specific formats for it to be accepted by the data base. Three data input programs are used to prepare data for the specific formats: PAVERIN, EDITOR, and REFORMAT. All of these programs have been written in BASIC computer language and are operable on a personal computer that contains a BASIC system. The PAVERIN program is used to input the data into the correct formats. The EDITOR program is used for editing any errors that may have been placed in the data. The REFORMAT program is used to prepare the data for uploading onto the mainframe computer.

* M. Y. Shahin. 1985. "The PAVER User's Guide," ADP-356-1, US Army Construction Engineering Research Laboratory and US Army Facilities Engineering Support Agency.

16. The two ways to collect the condition survey data in the field are by recording the data manually on condition survey data sheets and later placing the data into PAVER format using the PAVERIN data input program, or by inputting the data directly into the FIELD program on a portable computer. The FIELD program places the data into PAVER format as the data are entered into the computer and saves the data in a field that can be directly uploaded to the mainframe computer. The PCI data obtained for Davis-Monthan AFB were recorded manually on condition survey sheets and placed into the PAVER format using the PAVERIN data input program.

17. The physical properties and construction history data on the pavements at Davis-Monthan AFB were obtained from the 1989 Tyndall evaluation report and from base engineering personnel.

System Sign-On

18. The mainframe PAVER system currently resides on a Control Data Corporation (CDC) computer and is accessible through a remote terminal via a telephone link. The telephone link is achieved by using a modem and appropriate communication software. Connection to the system requires dialing the CDC computer for connection and then entering the appropriate access codes to sign-on the computer. The access codes (user ID, password, and charge number) are obtained when a charge account has been set up with CDC. The access codes for use in accessing the data once arrangements have been made with CDC are as follows:

Family:	KOE
User ID:	FBNVPVR
Password:	XTACDMT
Charge:	Charge, CEAHE3A, PAVEDMT

The "call access" password is DAVIS.

Data Upload and Data Base Update

19. Data are added to the data base either interactively or by using the BATCH method. The interactive method is used when the user is on-line to the CDC computer. This method is easier to perform but is more expensive. Using BATCH involves transferring the data file created with the PAVERIN or

FIELD programs from the personal computer to the CDC mainframe. Using either operation involves creating the file DATAFL on the CDC computer from which the data are read into the data base. After DATAFL is prepared, the PAVER system checks it for errors, and after corrections have been made, the data are loaded into the data base.

Report Generation and Data Analysis

20. The PAVER system generates reports that provide a summary of specific information based on the data stored in the mainframe data base. It also calculates information such as budget needs from data and analysis programs provided by PAVER. These reports can be generated either interactively or through a BATCH process. The BATCH process produces the report when the user is not signed-on to the CDC computer and is more cost-effective when generating large amounts of information. The interactive process, performed while the user is signed-on, can be used effectively when generating smaller reports and detecting data base errors.

21. There are two types of data analysis programs in the PAVER system: those that access the data base, and those that do not access the data base. The difference in the two types is that the data base must be on line for the report to operate. The user responds to questions that the program asks, and then analysis results are produced based on those responses. The analysis reports can only be generated using the interactive process.

22. The data reports and analysis programs derived from PAVER provide information needed to make pavement management decisions. The following reports were generated from the completed data base and are included herein as Appendix A.

- a. LIST--Report showing a summary of all branches in the data base.
- b. INV--Inventory report showing all sections in the data base.
- c. PCI--Pavement condition index report for all pavement sections in the data base.
- d. SCHED--Inspection schedule report on the branches (features) which should be reinspected during the next year based on a minimum of 70 PCI and rate of deterioration.
- e. SAMPCUR--The current inspection results for each branch detailed by sample units.

LEGEND

FEATURE DESIGNATION (SEE PAVEMENT THICKNESS IN)

TYPE OF FEATURE

R --- RUNWAY

T --- TAXIWAY

A --- APRON

TYPE TRAFFIC AREA (SEE NOTE)

A --- A TYPE TRAFFIC

B --- B TYPE TRAFFIC

C --- C TYPE TRAFFIC


D --- D TYPE TRAFFIC

--- CHANGE IN FEATURE DESIGNATION

PCC PORTLAND CEMENT CONCRETE

AC ASPHALTIC CONCRETE

S STRESS ABSORBING MEMBRANE INT



DAVIS-MONTHAN AFEN

FIGURE 1, BRANCH IDENTIFICATION

LEGEND



FEATURE DESIGNATION (SEE NOTE 1)
PAVEMENT THICKNESS IN INCHES & TYPE

TYPE OF FEATURE

R -- RUNWAY

T -- TAXIWAY

A -- APRON

TYPE TRAFFIC AREA (SEE NOTE 2)

A -- A TYPE TRAFFIC

B -- B TYPE TRAFFIC

C -- C TYPE TRAFFIC

D -- D TYPE TRAFFIC

----- CHANGE IN FEATURE DESIGNATION


PCC PORTLAND CEMENT CONCRETE

AC ASPHALTIC CONCRETE


S STRESS ABSORBING MEMBRANE INTERLAYER (.5)

NOTES

1. FEATURE DESIGNATION DENOTES TYPE OF FEATURE, NUMBER OF FEATURE FOR GIVEN FEATURE TYPE AND TYPE TRAFFIC AREA.
2. TRAFFIC AREA DESIGNATIONS ARE BASED ON AFM 88-6, CHAPTER 1.
3. FEATURE DESIGNATIONS DO NOT CORRESPOND WITH THOSE FROM PREVIOUS REPORTS AND DRAWINGS.



ENTHAN AFB, ARIZONA



GRAPHIC SCALE IN FEET

DEPARTMENT OF THE AIR FORCE		DAVIS - MONTGOMERY AFB, AL		NAME OF		TITLE	
TECHNICAL AIR CREW		UNIT		NAME OF		TITLE	
OFFICE		DATE		NAME OF		TITLE	
DATE		DATE		NAME OF		TITLE	
DATE		DATE		NAME OF		TITLE	

1. BRANCH IDENTIFICATION







FIGURE 2, SAMPLE UNIT LOCATION ON BRANCHES R1A, R6D, AR7C, R8C, R15A, R16A, R17C, R18C, R23C, R25D, AND R26D.













FIGURE 4, SAMPLE UNIT LOCATION ON BRANCHES R1
R28D, R29D, R33D, R34D, R35C, R36D AND R40C.



UNIT LOCATION ON BRANCHES R10C, R21C, R34D, R35C, R36D AND R40C.



DEPARTMENT OF THE AIR FORCE	BRANCH R34D, R35C, R36D, R40C
UNIT LOCATION ON BRANCHES	PCI
DATE	RWY 12-30






FIGURE 5, SAMPLE UNIT LOCATION ON BRANCHES R10C, R11C, R12C, R13A, R14A, R24C, R28D, R36D, R37D, R38C AND R40C.






FIGURE 6, SAMPLE UNIT LOCATION ON BRANCHES T3A, T5A, T20A, T21A, T24A, T33A, T41A, AND A39B.



SA, UNIT LOCATION ON BRANCHES T3A, T4A, T4A, T33A, T41A, AND A39B.



DEPARTMENT OF THE AIR FORCE		BRANCH-RESEARCH AVIATION	
PROJECT: T3A, T4A, T4A, T33A, T41A, AND A39B		PROJECT: T3A, T4A, T4A, T33A, T41A, AND A39B	
DATE: 1964		DATE: 1964	
BY: [Signature]		BY: [Signature]	
CHECKED: [Signature]		CHECKED: [Signature]	
APPROVED: [Signature]		APPROVED: [Signature]	
T3A, T4A, T4A, T33A, T41A, AND A39B		T3A, T4A, T4A, T33A, T41A, AND A39B	







FIGURE 7, SAMPLE UNIT LOCATIONS ON BRANCHES T3A, T4A, T5A, T6A, T20A, T21A, T33A, T41A, AND A35B.





UNIT LOCATION ON BRANCHES
T32A, T36A, T41A, AND T35B.



DEPARTMENT OF THE ARMY ENGINEER REGIMENT T32A, T36A, T41A, AND T35B		BRIDGE NUMBER AND LOCATION T32A, T36A, T41A, AND T35B	
DRAWN BY T32A, T36A, T41A, AND T35B		CHECKED BY T32A, T36A, T41A, AND T35B	
DATE T32A, T36A, T41A, AND T35B		SCALE T32A, T36A, T41A, AND T35B	





FIGURE 9. SAMPLE UNIT LOCATION ON BRANCHES T3A, T4A, T5A, T6A, T7A, T8A, T9A, T18B, T34A, T35A, AND A18B.



DEPARTMENT OF THE AIR FORCE OFFICE OF THE SECRETARY		AIR FORCE OFFICE OF THE SECRETARY	
NAME (Last, first, middle initial) TITLE		NAME (Last, first, middle initial) TITLE	
ADDRESS CITY STATE		ADDRESS CITY STATE	







FIGURE 10. SAMPLE UNIT LOCATION ON BRANCHES T10A AND A10B



ON BRANCHES T10A AND A10B.



DEPARTMENT OF THE AIR FORCE		A10B	
TAXIWAY 20		TAXIWAY 20	
PCI		PCI	
TAXIWAY 20		TAXIWAY 20	






FIGURE 11, SAMPLE UNIT LOCATION ON BRANCH
A2B, A23B, A37B, A45B, A66B, T1A, T26C, A



TAXIWAY 15A

NO SAMPLE UNIT LOCATION ON BRANCHES A1B,
A37B, A45B, A66B, T1A, T26C, AND T40B.



REVISIONS OF THIS PLAN	DATE	BY	APP. BY
1	10/1/68	J. H. BAC	J. H. BAC
TAXIWAY 15 & TWY 15A			






FIGURE 12. SAMPLE UNIT LOCATION ON BRANCHES T14C AND



LOCATION ON BRANCHES T14C AND T16C.



DATE OF SURVEY	DATE OF SURVEY
BY	BY
FOR	FOR
PROJECT	PROJECT
PC1	PC1
TW116 & TW117	TW116 & TW117




FIGURE 13, SAMPLE UNIT LOCATION ON BRANCHES T27C,

DATE: 10/10/80		TIME: 1400	
FROM: PCJ		TO: JAB/AC	
SUBJECT: TWY 1		PAGE: 1	





FIGURE 14,



MATCH SHT. 4

SUNFLOW ROAD






FIGURE 15, SAMPLE UNIT LOCATION (A27B, A28B, A29B, A30B, AND A31B)



SURVEY WAS PERFORMED ON THE PORTIONS OF FEATURES SHOWN ON THIS SHEET.

FIGURE 15, SAMPLE UNIT LOCATION ON BRANCHES
7B, A28B, A29B, A30B, AND A31B.



PCI
NORTH RAMP







FIGURE 17, SAMPLE UNIT LOCATION ON BRANCHES A19B, A21B, A24B, A25B, A26B, A33B, A50B, A57B, A87B, A88B, A89B, AND T23C.





MATCH SHT. 7

UNIT LOCATION ON BRANCHES
A57B, A60B, A61B, A62B, AND A63B.



UNIT	BRANCH	TYPE	DATE	BY	CHECKED	APPROVED
A57B	PCI	WEST RAMP				
A60B	PCI	WEST RAMP				
A61B	PCI	WEST RAMP				
A62B	PCI	WEST RAMP				
A63B	PCI	WEST RAMP				







FIGURE 19. SAMPLE UNIT LOCATION ON BRANCHES T2C, T23C, T42C, A47B AND A4





MATCH SHT. 8

INIT LOCATION ON BRANCHES
A38B, A39B, AND A49B.



DEPARTMENT OF THE AIR FORCE		ENGINEERING DIVISION	
TERRAIN & SURVEY		AERIAL PHOTOGRAPHY	
PROJECT: _____		DATE: 11/10/54	
SHEET: _____		DRAWN BY: _____	
OPERATIONAL APRON		PCI	






FIGURE 21, SAMPLE UNIT LOCATION ON BRANCHE, A5B, A41B, A42B, AND A43B.



AMPLE UNIT LOCATION ON BRANCHES
42B, AND A43B.



PREPARED BY DATE CHECKED BY DATE	DRAWN BY DATE OPERATIONAL APRON	PROJECT NO. DRAWING NO. SHEET NO.
---	---------------------------------------	---






FIGURE 22, SAMPLE UNIT LOCATION ON BRANCHES A5B, A6B, AN



MATCH SHEET

ATION ON BRANCHES A5B, A6B, AND A42B.



DEPARTMENT OF THE AIR FORCE		ENGINEERING ATTACHMENT	
TOWNSHIP OF SHERBORN		MASSACHUSETTS	
OPERATIONAL APRON		PCI	





FIGURE 23, SAMPLE UNIT LOCATION ON BRANCHES A6B, A7B



71 LOCATION ON BRANCHES A6B, A7B AND A8B.



GRAPHIC SCALE IN FEET

OFFICE OF THE AIR FORCE		AIR FORCE COMMAND	
HEADQUARTERS, AIR FORCE		HEADQUARTERS, AIR FORCE	
PC1		PC1	
OPERATIONAL APRON		OPERATIONAL APRON	




FIGURE 24. SAMPLE UNIT LOCATION ON BRANCHES A13B, A14B, A15B, A16B, AND A





FIGURE 25, SAMPLE UNIT LOCATION ON BRANCHES T11C



T LOCATION ON BRANCHES T11C, A11B, A12B.



GRAPHIC SCALE IN FEET

APPROVED BY	DATE	REVISION
DESIGNED BY	DATE	REVISION
CHECKED BY	DATE	REVISION
PROJECT NAME	DATE	REVISION
PC1		
TWY 21 & TWY 22		
UNIVERSITY PARK		

WATER SHED






FIGURE 26, SAMPLE UNIT LOCATION ON BRANCHES T11C, A11B, AND A10N



A10N BRANCHES T11C, A11B, AND A12B.



DATE	BY	REVISION
10/1/78	J. J. J.	1
10/1/78	J. J. J.	2
10/1/78	J. J. J.	3
10/1/78	J. J. J.	4
10/1/78	J. J. J.	5
10/1/78	J. J. J.	6
10/1/78	J. J. J.	7
10/1/78	J. J. J.	8
10/1/78	J. J. J.	9
10/1/78	J. J. J.	10
10/1/78	J. J. J.	11
10/1/78	J. J. J.	12
10/1/78	J. J. J.	13
10/1/78	J. J. J.	14
10/1/78	J. J. J.	15
10/1/78	J. J. J.	16
10/1/78	J. J. J.	17
10/1/78	J. J. J.	18
10/1/78	J. J. J.	19
10/1/78	J. J. J.	20
10/1/78	J. J. J.	21
10/1/78	J. J. J.	22
10/1/78	J. J. J.	23
10/1/78	J. J. J.	24
10/1/78	J. J. J.	25
10/1/78	J. J. J.	26
10/1/78	J. J. J.	27
10/1/78	J. J. J.	28
10/1/78	J. J. J.	29
10/1/78	J. J. J.	30
10/1/78	J. J. J.	31
10/1/78	J. J. J.	32
10/1/78	J. J. J.	33
10/1/78	J. J. J.	34
10/1/78	J. J. J.	35
10/1/78	J. J. J.	36
10/1/78	J. J. J.	37
10/1/78	J. J. J.	38
10/1/78	J. J. J.	39
10/1/78	J. J. J.	40
10/1/78	J. J. J.	41
10/1/78	J. J. J.	42
10/1/78	J. J. J.	43
10/1/78	J. J. J.	44
10/1/78	J. J. J.	45
10/1/78	J. J. J.	46
10/1/78	J. J. J.	47
10/1/78	J. J. J.	48
10/1/78	J. J. J.	49
10/1/78	J. J. J.	50
10/1/78	J. J. J.	51
10/1/78	J. J. J.	52
10/1/78	J. J. J.	53
10/1/78	J. J. J.	54
10/1/78	J. J. J.	55
10/1/78	J. J. J.	56
10/1/78	J. J. J.	57
10/1/78	J. J. J.	58
10/1/78	J. J. J.	59
10/1/78	J. J. J.	60
10/1/78	J. J. J.	61
10/1/78	J. J. J.	62
10/1/78	J. J. J.	63
10/1/78	J. J. J.	64
10/1/78	J. J. J.	65
10/1/78	J. J. J.	66
10/1/78	J. J. J.	67
10/1/78	J. J. J.	68
10/1/78	J. J. J.	69
10/1/78	J. J. J.	70
10/1/78	J. J. J.	71
10/1/78	J. J. J.	72
10/1/78	J. J. J.	73
10/1/78	J. J. J.	74
10/1/78	J. J. J.	75
10/1/78	J. J. J.	76
10/1/78	J. J. J.	77
10/1/78	J. J. J.	78
10/1/78	J. J. J.	79
10/1/78	J. J. J.	80
10/1/78	J. J. J.	81
10/1/78	J. J. J.	82
10/1/78	J. J. J.	83
10/1/78	J. J. J.	84
10/1/78	J. J. J.	85
10/1/78	J. J. J.	86
10/1/78	J. J. J.	87
10/1/78	J. J. J.	88
10/1/78	J. J. J.	89
10/1/78	J. J. J.	90
10/1/78	J. J. J.	91
10/1/78	J. J. J.	92
10/1/78	J. J. J.	93
10/1/78	J. J. J.	94
10/1/78	J. J. J.	95
10/1/78	J. J. J.	96
10/1/78	J. J. J.	97
10/1/78	J. J. J.	98
10/1/78	J. J. J.	99
10/1/78	J. J. J.	100

PCI
WHISKEY RAMP

**PAVEMENT CONDITION
INDEX (PCI)**

**PAVEMENT CONDITION
RATING**




Figure 27. PCI scale




Photo 1. Overall view of Runway 12-30
looking northwest



Photo 2. Typical patching on R12C



Photo 3. Typical longitudinal/transverse cracks on R13A



Photo 4. Typical shattered slab on R13A




Photo 5. Utility cut on R17C



Photo 6. Typical longitudinal/transverse
cracks on R19C



Photo 7. Overall view of R24C




Photo 8. Typical longitudinal/transverse
crack on R38C



Photo 9. Typical joint seal damage on T1A



Photo 10. Large patch on T1A



Photo 11. Overall view of T10A




Photo 12. Typical patch on T11C




Photo 13. Block cracking on T15C




Photo 14. Typical map cracking on T23C




Photo 15. Typical longitudinal/transverse
cracks on T23C




Photo 16. Overall view of T27C



Photo 17. Large patch on A4B



Photo 18. Overall view of A5B




Photo 19. Small patch on A5B




Photo 20. Overall view of A6B




Photo 21. Utility cut on A6B




Photo 22. Typical joint spalling on A11B



Photo 23 Shattered slab on A12B



Photo 24 Overall view of A25B




Photo 25. Typical patch on A45B




Photo 26 Longitudinal/transverse
cracks on A65B

APPENDIX A: DATA REPORTS AND ANALYSIS PROGRAMS

BRANCH LISTING

REPORT DATE- 11/02/89

DAVIS-MONTHAN AIR FORCE BASE

BRANCH NUMBER	BRANCH NAME	NUMBER OF SECTIONS
R1A	RUNWAY 12-30	1
R6D	RUNWAY 12-30	1
R7C	RUNWAY 12-30	1
R8C	RUNWAY 12-30	1
R10C	RUNWAY 12-30	1
R11C	RUNWAY 12-30	1
R12C	RUNWAY 12-30	1
R13A	RUNWAY 12-30	1
R14A	RUNWAY 12-30	1
R15A	RUNWAY 12-30	1
R16A	RUNWAY 12-30	1
R17C	RUNWAY 12-30	1
R18C	RUNWAY 12-30	1
R19C	RUNWAY 12-30	1
R21C	RUNWAY 12-30	1
R22C	RUNWAY 12-30	1
R23C	RUNWAY 12-30	1
R24C	RUNWAY 12-30	1
R25D	RUNWAY 12-30	1
R26D	RUNWAY 12-30	1
R27D	RUNWAY 12-30	1
R28D	RUNWAY 12-30	1
R29D	RUNWAY 12-30	1
R30C	RUNWAY 12-30	1
R31C	RUNWAY 12-30	1
R32D	RUNWAY 12-30	1
R33D	RUNWAY 12-30	1
R34D	RUNWAY 12-30	1
R35C	RUNWAY 12-30	1
R36D	RUNWAY 12-30	1
R37D	RUNWAY 12-30	1
R38C	RUNWAY 12-30	1
R39C	RUNWAY 12-30	1
R40C	RUNWAY 12-30	1
T1A	T/W 15	1
T3A	T/W 14	1
T4A	T/W 14	1
T5A	T/W 14	1
T6A	T/W 14	1
T7A	T/W 14	1
T8A	T/W 14	1
T9A	T/W 14	1
T10A	T/W 20	1
T11C	T/W 22	1
T14C	T/W 16	1

T16C	T/W 17	1
T17C	T/W 18	1
T18C	COMPASS ROSE	1
T19A	ALERT T/W	1
T20A	LADDER T/W	1
T21A	T/W 19	1
T22C	T/W 24	1
T23C	T/W 3	1
T24C	POWER CK PAD T/W	1
T26C	T/W 15A	1
T27C	T/W 1	1
T32A	T/W 19	1
T33A	LADDER T/W	1
T34A	T/W 14	1
T35A	T/W 14	1
T36A	LADDER T/W	1
T40C	PWR CK PAD T/W	1
T41A	LADDER T/W	1
T42C	T/W 3	1
A1B	T/W 15 WARMUP	1
A2B	T/W 15 WARMUP	1
A3B	OPERATIONAL APRON	1
A4B	OPERATIONAL APRON	1
A5B	OPERATIONAL APRON	1
A6B	OPERATIONAL APRON	1
A7B	OPERATIONAL APRON	1
A8B	OPERATIONAL APRON	1
A9B	WARMUP APRON	1
A10B	WARMUP	1
A11B	CHRISTMAS TREE APRON	1
A12B	CHRISTMAS TREE APRON	1
A13B	ALERT APRON	1
A14B	ALERT APRON	1
A15B	MAINTENANCE APRON	1
A16B	MAINTENANCE APRON	1
A17B	MAINTENANCE APRON	1
A18B	COMPASS ROSE	1
A19B	WEST APRON	1
A21B	WEST APRON	1
A22B	NORTH APRON	1
A23B	HARD STAND	1
A24B	NORTH APRON	1
A25B	NORTH APRON	1
A26B	NORTH APRON	1
A28B	NORTH APRON	1
A29B	NORTH APRON	1
A30B	NORTH APRON	1
A33B	NORTH APRON	1
A35B	OPERATIONAL APRON	1
A38B	BLDG APRON	1
A39B	BLDG APRON	1
A40B	DANGEROUS CARGO PAD	1
A45B	APRON	1
A47B	HANGAR APRON	1

A48B	HANGAR APRON	1
A49B	WASHRACK	1
A50B	NORTH APRON	1
A51B	WEST APRON	1
A52B	WEST APRON	1
A57B	BLDG APRON	1
A59B	HANGAR APRON	1
A60B	HANGAR APRON	1
A61B	HANGAR APRON	1
A63B	HANGAR APRON	1
A64B	POWER TRIM APRON	1
A65B	POWER TRIM APRON	1
A66B	APRON	1

AGENCY NUMBER -

1 DAVIS-MONTHAN AF BASE

INVENTORY

REPORT DATE- 11/02/89

DAVIS-MONTHAN AFB
SECTION CATEGORY TYPE

		SURF TYPE	BRANCH USE	PAVEMENT RANK	AREA (SY)

R1A	RUNWAY 12-30 SECTION 1 FROM- 0+00 TO- 3+00	PCC	RUNWAY	PRIMARY	6667
				TOTAL BRANCH AREA	6667

R6D	RUNWAY 12-30 SECTION 1 FROM-10+00 TO-11+90 FROM-12+10 TO-27+00	AC	RUNWAY	PRIMARY	10080
				TOTAL BRANCH AREA	10080

R7C	RUNWAY 12-30 SECTION 1 FROM-27+00 TO- 35+00	AC	RUNWAY	PRIMARY	8889
				TOTAL BRANCH AREA	8889

R8C	RUNWAY 12-30 SECTION 1 FROM-31+00 TO- 34+00	AC	RUNWAY	PRIMARY	1667
				TOTAL BRANCH AREA	1667

R10C	RUNWAY 12-30 SECTION 1 FROM-91+50 TO- 112+00	AC	RUNWAY	PRIMARY	8782
				TOTAL BRANCH AREA	8782

R11C	RUNWAY 12-30 SECTION 1 FROM-112+00 TO- 115+00	PCC	RUNWAY	PRIMARY	6667
				TOTAL BRANCH AREA	6667

R12C	RUNWAY 12-30 SECTION 1 FROM-115+00 TO- 124+20	PCC	RUNWAY	PRIMARY	20444
				TOTAL BRANCH AREA	20444

R13A	RUNWAY 12-30 SECTION 1 FROM-126+45 TO- 124+70	PCC	RUNWAY	PRIMARY	15000	
					TOTAL BRANCH AREA	15000

R14A	RUNWAY 12-30 SECTION 1 FROM-131+45 TO- 136+45	PCC	RUNWAY	PRIMARY	11111	
					TOTAL BRANCH AREA	11111

R15A	RUNWAY 12-30 SECTION 1 FROM- 3+00 TO- 5+00	PCC	RUNWAY	PRIMARY	4444	
					TOTAL BRANCH AREA	4444

R16A	RUNWAY 12-30 SECTION 1 FROM- 5+00 TO- 10+00	PCC	RUNWAY	PRIMARY	11111	
					TOTAL BRANCH AREA	11111

R17C	RUNWAY 12-30 SECTION 1 FROM- 10+00 TO- 11+90 FROM- 12+10 TO- 27+00	PCC	RUNWAY	PRIMARY	14000	
					TOTAL BRANCH AREA	14000

R18C	RUNWAY 12-30 SECTION 1 FROM- 10+00 TO- 11+90 FROM- 12+10 TO- 27+00	AC	RUNWAY	PRIMARY	3173	
					TOTAL BRANCH AREA	3173

R19C	RUNWAY 12-30 SECTION 1 FROM- 35+00 TO- 45+00	AC	RUNWAY	PRIMARY	11111	
					TOTAL BRANCH AREA	11111

R21C	RUNWAY 12-30 SECTION 1 FROM- 65+00 TO- 80+00	AC	RUNWAY	PRIMARY	16667	
					TOTAL BRANCH AREA	16667

R22C	RUNWAY 12-30 SECTION 1 FROM- 45+00 TO- 56+00	AC	RUNWAY	PRIMARY	12222	
					TOTAL BRANCH AREA	12222

R23C	RUNWAY 12-30					

SECTION 1	PCC	RUNWAY	PRIMARY	444
FROM- 11+90				
TO- 12+10				
TOTAL BRANCH AREA				444

R24C RUNWAY 12-30				
SECTION 1	PCC	RUNWAY	PRIMARY	1111
FROM-124+20				
TO- 124+70				
TOTAL BRANCH AREA				1111

R25D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	14880
FROM- 10+00 TO- 11+90				
FROM- 12+10 TO- 35+00				
TOTAL BRANCH AREA				14880

R26D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	2222
FROM- 27+00				
TO- 31+00				
TOTAL BRANCH AREA				2222

R27D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	556
FROM- 34+00				
TO- 35+00				
TOTAL BRANCH AREA				556

R28D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	11472
FROM- 84+85				
TO- 105+50				
TOTAL BRANCH AREA				11472

R29D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	39444
FROM-35+00				
TO- 70+00				
TOTAL BRANCH AREA				39444

R30C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	5000
FROM- 56+00				
TO- 65+00				
TOTAL BRANCH AREA				5000

R31C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	5000
FROM- 56+00				
TO- 65+00				
TOTAL BRANCH AREA				5000

R32D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	5000

FROM- 56+00				
TO- 65+00				
-----			TOTAL BRANCH AREA	5000
R33D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	5556
FROM- 70+00				
TO- 80+00				
-----			TOTAL BRANCH AREA	5556
R34D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	556
FROM- 80+00				
TO- 81+00				
-----			TOTAL BRANCH AREA	556
R35C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	2139
FROM- 81+00				
TO- 84+85				
-----			TOTAL BRANCH AREA	2139
R36D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	17778
FROM- 80+00				
TO- 112+00				
-----			TOTAL BRANCH AREA	17778
R37D RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	3611
FROM-105+50				
TO- 112+00				
-----			TOTAL BRANCH AREA	3611
R38C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	3611
FROM-105+00				
TO- 112+00				
-----			TOTAL BRANCH AREA	3611
R39C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	2607
FROM- 91+50				
TO- 103+23				
-----			TOTAL BRANCH AREA	2607
R40C RUNWAY 12-30				
SECTION 1	AC	RUNWAY	PRIMARY	20556
FROM- 80+00				
TO- 105+50				
-----			TOTAL BRANCH AREA	20556
T1A T/W 15				
SECTION 1	PCC	TAXIWAY	PRIMARY	5139
FROM- 0+00				

TO- 9+25

				TOTAL BRANCH AREA	5139

T3A	T/W 14				
	SECTION 1	AC	TAXIWAY	PRIMARY	25988
				TOTAL BRANCH AREA	25988

T4A	T/W 14				
	SECTION 1	AC	TAXIWAY	PRIMARY	18528
				TOTAL BRANCH AREA	18528

T5A	T/W 14				
	SECTION 1	PCC	TAXIWAY	PRIMARY	25556
				TOTAL BRANCH AREA	25556

T6A	T/W 14				
	SECTION 1	PCC	TAXIWAY	PRIMARY	25556
				TOTAL BRANCH AREA	25556

T7A	T/W 14				
	SECTION 1	AC	TAXIWAY	PRIMARY	3990
				TOTAL BRANCH AREA	3990

T8A	T/W 14				
	SECTION 1	AC	TAXIWAY	PRIMARY	1470
				TOTAL BRANCH AREA	1470

T9A	T/W 14				
	SECTION 1	PCC	TAXIWAY	PRIMARY	3780
				TOTAL BRANCH AREA	3780

T10A	T/W 20				
	SECTION 1	PCC	TAXIWAY	PRIMARY	10000
				TOTAL BRANCH AREA	10000

T11C	T/W 22				
	SECTION 1	PCC	TAXIWAY	SECONDARY	21667
				TOTAL BRANCH AREA	21667

T14C	T/W 16				
	SECTION 1	AC	TAXIWAY	SECONDARY	7083
				TOTAL BRANCH AREA	7083

T16C	T/W 17				
	SECTION 1	PCC	TAXIWAY	SECONDARY	12500

				TOTAL BRANCH AREA	12500

T17C	T/W 18				
	SECTION 1	AC	TAXIWAY	SECONDARY	7083
				TOTAL BRANCH AREA	7083

T18C	COMPASS ROSE				
	SECTION 1	PCC	TAXIWAY	SECONDARY	2083
				TOTAL BRANCH AREA	2083

T19A	ALERT T/W				
	SECTION 1	AC	TAXIWAY	PRIMARY	10000
				TOTAL BRANCH AREA	10000

T20A	LADDER T/W				
	SECTION 1	PCC	TAXIWAY	PRIMARY	25000
				TOTAL BRANCH AREA	25000

T21A	T/W 19				
	SECTION 1	AC	TAXIWAY	PRIMARY	36875
				TOTAL BRANCH AREA	36875

T22C	T/W 24				
	SECTION 1	AC	TAXIWAY	SECONDARY	12167
				TOTAL BRANCH AREA	12167

T23C	T/W 3				
	SECTION 1	PCC	TAXIWAY	SECONDARY	30000
				TOTAL BRANCH AREA	30000

T24C	POWER CK PAD T/W				
	SECTION 1	PCC	TAXIWAY	SECONDARY	889
				TOTAL BRANCH AREA	889

T26C	T/W 15A				
	SECTION 1	AC	TAXIWAY	SECONDARY	4528
				TOTAL BRANCH AREA	4528

T27C	T/W 1				
	SECTION 1	AC	TAXIWAY	SECONDARY	12500
				TOTAL BRANCH AREA	12500

T32A	T/W 19				
	SECTION 1	PCC	TAXIWAY	PRIMARY	9294

			TOTAL BRANCH AREA	9294

T33A	LADDER T/W			
	SECTION 1	AC	TAXIWAY PRIMARY	9583
			TOTAL BRANCH AREA	9583

T34A	T/W 14			
	SECTION 1	PCC	TAXIWAY PRIMARY	4708
			TOTAL BRANCH AREA	4708

T35A	T/W 14			
	SECTION 1	PCC	TAXIWAY PRIMARY	5375
			TOTAL BRANCH AREA	5375

T36A	LADDER T/W			
	SECTION 1	PCC	TAXIWAY PRIMARY	11250
			TOTAL BRANCH AREA	11250

T40C	PWR CK PAD T/W			
	SECTION 1	PCC	TAXIWAY SECONDARY	1133
			TOTAL BRANCH AREA	1133

T41A	LADDER T/W			
	SECTION 1	PCC	TAXIWAY PRIMARY	11076
			TOTAL BRANCH AREA	11076

T42C	T/W 3			
	SECTION 1	PCC	TAXIWAY SECONDARY	1542
			TOTAL BRANCH AREA	1542

A1B	T/W 15 WARMUP			
	SECTION 1	PCC	APRON SECONDARY	9375
			TOTAL BRANCH AREA	9375

A2B	T/W 15 WARMUP			
	SECTION 1	PCC	APRON SECONDARY	5556
			TOTAL BRANCH AREA	5556

A3B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON PRIMARY	17500
			TOTAL BRANCH AREA	17500

A4B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON PRIMARY	10000
			TOTAL BRANCH AREA	10000

A5B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON	PRIMARY
				316956
			TOTAL	BRANCH AREA
				316956

A6B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON	PRIMARY
				64167
			TOTAL	BRANCH AREA
				64167

A7B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON	PRIMARY
				79722
			TOTAL	BRANCH AREA
				79722

A8B	OPERATIONAL APRON			
	SECTION 1	PCC	APRON	SECONDARY
				5678
			TOTAL	BRANCH AREA
				5678

A9B	WARMUP APRON			
	SECTION 1	AC	APRON	SECONDARY
				14933
			TOTAL	BRANCH AREA
				14933

A10B	WARMUP			
	SECTION 1	PCC	APRON	SECONDARY
				15556
			TOTAL	BRANCH AREA
				15556

A11B	CHRISTMAS TREE APRON			
	SECTION 1	PCC	APRON	SECONDARY
				37500
			TOTAL	BRANCH AREA
				37500

A12B	CHRISTMAS TREE APRON			
	SECTION 1	PCC	APRON	SECONDARY
				25000
			TOTAL	BRANCH AREA
				25000

A13B	ALERT APRON			
	SECTION 1	PCC	APRON	SECONDARY
				667
			TOTAL	BRANCH AREA
				667

A14B	ALERT APRON			
	SECTION 1	PCC	APRON	SECONDARY
				14583
			TOTAL	BRANCH AREA
				14583

A15B	MAINTENANCE APRON			
	SECTION 1	PCC	APRON	SECONDARY
				2500
			TOTAL	BRANCH AREA
				2500

A16B	MAINTENANCE APRON			
	SECTION 1	PCC	APRON	SECONDARY
				3333

				TOTAL BRANCH AREA	3333

A17B	MAINTENANCE APRON	AC	APRON	SECONDARY	24333
	SECTION 1				
				TOTAL BRANCH AREA	24333

A18B	COMPASS ROSE	PCC	APRON	SECONDARY	1963
	SECTION 1				
				TOTAL BRANCH AREA	1963

A19B	WEST ARPON	PCC	APRON	SECONDARY	68056
	SECTION 1				
				TOTAL BRANCH AREA	68056

A21B	WEST APRON	PCC	APRON	SECONDARY	14208
	SECTION 1				
				TOTAL BRANCH AREA	14208

A22B	NORTH APRON	PCC	APRON	SECONDARY	3333
	SECTION 1				
				TOTAL BRANCH AREA	3333

A23B	HARD STAND	PCC	APRON	SECONDARY	89
	SECTION 1				
				TOTAL BRANCH AREA	089

A24B	NORTH APRON	PCC	APRON	SECONDARY	3958
	SECTION 1				
				TOTAL BRANCH AREA	3958

A25B	NORTH APRON	PCC	APRON	SECONDARY	15611
	SECTION 1				
				TOTAL BRANCH AREA	15611

A26B	NORTH APRON	PCC	APRON	SECONDARY	19167
	SECTION 1				
				TOTAL BRANCH AREA	19167

A28B	NORTH APRON	PCC	APRON	SECONDARY	18333
	SECTION 1				
				TOTAL BRANCH AREA	18333

A29B	NORTH APRON	PCC	APRON	SECONDARY	12222
	SECTION 1				

-----				TOTAL BRANCH AREA	12222
A30B NORTH APRON					
SECTION 1	PCC	APRON	SECONDARY	24444	
-----				TOTAL BRANCH AREA	24444
A33B NORTH APRON					
SECTION 1	PCC	APRON	SECONDARY	10000	
-----				TOTAL BRANCH AREA	10000
A35B OPERATIONAL APRON					
SECTION 1	PCC	APRON	SECONDARY	30831	
-----				TOTAL BRANCH AREA	30831
A38B BLDG APRON					
SECTION 1	PCC	APRON	SECONDARY	2177	
-----				TOTAL BRANCH AREA	2177
A39B BLDG APRON					
SECTION 1	PCC	APRON	SECONDARY	1250	
-----				TOTAL BRANCH AREA	1250
A40B DANGEROUS CARGO PAD					
SECTION 1	AC	APRON	SECONDARY	51111	
-----				TOTAL BRANCH AREA	51111
A45B APRON					
SECTION 1	PCC	APRON	SECONDARY	4861	
-----				TOTAL BRANCH AREA	4861
A47B HANGAR APRON					
SECTION 1	PCC	APRON	SECONDARY	1111	
-----				TOTAL BRANCH AREA	1111
A48B HANGAR APRON					
SECTION 1	PCC	APRON	SECONDARY	1250	
-----				TOTAL BRANCH AREA	1250
A49B WASHRACK					
SECTION 1	PCC	APRON	SECONDARY	3333	
-----				TOTAL BRANCH AREA	3333
A50B NORTH APRON					
SECTION 1	PCC	APRON	SECONDARY	3958	

				TOTAL BRANCH AREA	3958

A51B	WEST APRON	PCC	APRON	SECONDARY	1667
	SECTION 1				
				TOTAL BRANCH AREA	1667

A52B	WEST APRON	PCC	APRON	SECONDARY	1667
	SECTION 1				
				TOTAL BRANCH AREA	1667

A57B	BLDG APRON	PCC	APRON	SECONDARY	3333
	SECTION 1				
				TOTAL BRANCH AREA	3333

A59B	HANGAR APRON	AC	APRON	SECONDARY	8333
	SECTION 1				
				TOTAL BRANCH AREA	8333

A60B	HANGAR APRON	AC	APRON	SECONDARY	5556
	SECTION 1				
				TOTAL BRANCH AREA	5556

A61B	HANGAR APRON	AC	APRON	SECONDARY	83333
	SECTION 1				
				TOTAL BRANCH AREA	83333

A63B	HANGAR APRON	PCC	APRON	SECONDARY	8888
	SECTION 1				
				TOTAL BRANCH AREA	8888

A64B	POWER TRIM APRON	PCC	APRON	SECONDARY	1477
	SECTION 1				
				TOTAL BRANCH AREA	1477

A65B	POWER TRIM APRON	AC	APRON	SECONDARY	1667
	SECTION 1				
				TOTAL BRANCH AREA	1667

A66B	APRON	PCC	APRON	SECONDARY	2312
	SECTION 1				
				TOTAL BRANCH AREA	2312

TOTAL AREA OF SELECTED SECTION CATEGORY	PAVEMENTS	1,717,785
---	-----------	-----------

DAVIS-MONTHAN AFB PCI REPORT

BRANCH NUMBER/NAME	SECTION NUMBER	PAV. RANK	SURF. TYPE	SECTION AREA/SY	INSPECTION DATE	PCI
R1A *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] - 0+00	1	PRIMARY	PCC	6667 [TO] -3+00	09/01/89	36
R6D *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -10+00	1	PRIMARY	AC	10080 [TO] -27+00	09/02/89	77
R7C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -100' KEEL- 27+00	1	PRIMARY	AC	8889 [TO] -35+00	09/02/89	65
R8C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -31+00	1	PRIMARY	AC	1667 [TO] -34+00	09/02/89	72
R10C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -91+50	1	PRIMARY	AC	8782 [TO] -112+00	09/02/89	72
R11C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -112+00	1	PRIMARY	PCC	6667 [TO] -115+00	09/03/89	58
R12C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -115+00	1	PRIMARY	PCC	20444 [TO] -124+20	09/02/89	43
R13A *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -124+20	1	PRIMARY	PCC	15000 [TO] -131+45	09/03/89	58
R14A *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -131+45	1	PRIMARY	PCC	11111 [TO] -136+45	09/02/89	27
R15A *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -3+00	1	PRIMARY	PCC	4444 [TO] -5+00	09/02/89	77
R16A *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -5+00	1	PRIMARY	PCC	11111 [TO] -10+00	09/02/89	84
R17C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -10+00	1	PRIMARY	PCC	14000 [TO] -27+00	09/02/89	47
R18C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -10+00	1	PRIMARY	AC	3173 [TO] -27+00	09/02/89	74
R19C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -35+00	1	PRIMARY	AC	11111 [TO] -45+00	09/02/89	73
R21C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -65+00	1	PRIMARY	AC	16667 [TO] -80+00	09/02/89	69
R22C *RUNWAY 12-30 BRANCH USE- RUNWAY [FROM] -45+00	1	PRIMARY	AC	12222 [TO] -56+00	09/02/89	65

R23C *RUNWAY 12-30	1	PRIMARY	PCC	444	09/02/89	11
BRANCH USE- RUNWAY	[FROM] -11+90			[TO] -12+10		
R24C *RUNWAY 12-30	1	PRIMARY	PCC	1111	09/02/89	85
BRANCH USE- RUNWAY	[FROM] -124+20			[TO] -124+70		
R25D *RUNWAY 12-30	1	PRIMARY	AC	14880	09/02/89	71
BRANCH USE- RUNWAY	[FROM] -10+00			[TO] -35+00		
R26D *RUNWAY 12-30	1	PRIMARY	AC	2222	09/02/89	70
BRANCH USE- RUNWAY	[FROM] -27+00			[TO] -31+00		
R27D *RUNWAY 12-30	1	PRIMARY	AC	556	09/02/89	67
BRANCH USE- RUNWAY	[FROM] -34+00			[TO] -35+00		
R28D *RUNWAY 12-30	1	PRIMARY	AC	11472	09/02/89	69
BRANCH USE- RUNWAY	[FROM] -84+85			[TO] -105+50		
R29D *RUNWAY 12-30	1	PRIMARY	AC	39444	09/02/89	71
BRANCH USE- RUNWAY	[FROM] -35+00			[TO] -70+00		
R30C *RUNWAY 12-30	1	PRIMARY	AC	5000	09/02/89	69
BRANCH USE- RUNWAY	[FROM] -56+00			[TO] -65+00		
R31C *RUNWAY 12-30	1	PRIMARY	AC	5000	09/02/89	74
BRANCH USE- RUNWAY	[FROM] -56+00			[TO] -65+00		
R32D *RUNWAY 12-30	1	PRIMARY	AC	5000	09/02/89	71
BRANCH USE- RUNWAY	[FROM] -NE 50FT- 56+00			[TO] -65+00		
R33D *RUNWAY 12-30	1	PRIMARY	AC	5556	09/02/89	65
BRANCH USE- RUNWAY	[FROM] -SW 50FT- 70+00			[TO] -80+00		
R34D *RUNWAY 12-30	1	PRIMARY	AC	556	09/02/89	62
BRANCH USE- RUNWAY	[FROM] -NE 50FT- 80+00			[TO] -81+00		
R35C *RUNWAY 12-30	1	PRIMARY	AC	2139	09/02/89	44
BRANCH USE- RUNWAY	[FROM] -NE 50FT- 81+00			[TO] -84+85		
R36D *RUNWAY 12-30	1	PRIMARY	AC	17778	09/02/89	71
BRANCH USE- RUNWAY	[FROM] -SW 50FT- 80+00			[TO] -112+00		
R37D *RUNWAY 12-30	1	PRIMARY	AC	3611	09/02/89	66
BRANCH USE- RUNWAY	[FROM] -NE 50FT- 105+50			[TO] -112+00		
R38D *RUNWAY 12-30	1	PRIMARY	AC	3611	09/02/89	73
BRANCH USE- RUNWAY	[FROM] -SW OF CL 50FT-105+00			[TO] -112+00		
R39C *RUNWAY 12-30	1	PRIMARY	AC	2607	09/02/89	74
BRANCH USE- RUNWAY	[FROM] -20'W 30'NE CL-91+50			[TO] -103+23		
R40C *RUNWAY 12-30	1	PRIMARY	AC	12778	09/02/89	65
BRANCH USE- RUNWAY	[FROM] -100'KEEL- 80+00			[TO] - 91+50		
R40C *RUNWAY 12-30	1	PRIMARY	AC	7778	09/02/89	65

BRANCH USE- RUNWAY		[FROM] - 50'W SW CL 91+50	[TO] - 105+50					
T1A	*T/W 15	1	PRIMARY	PCC	5139	09/02/89	82	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T3A	*T/W 14	1	PRIMARY	AC	25988	09/02/89	100	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T4A	*T/W 14	1	PRIMARY	AC	18528	09/02/89	100	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T5A	*T/W 14	1	PRIMARY	PCC	25556	09/06/89	73	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T6A	*T/W 14	1	PRIMARY	PCC	25556	09/06/89	87	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T7A	*T/W 14	1	PRIMARY	AC	3990	09/06/89	100	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T8A	*T/W 14	1	PRIMARY	AC	1470	09/06/89	100	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T9A	*T/W 14	1	PRIMARY	PCC	3780	09/07/89	97	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T10A	*T/W 20	1	PRIMARY	PCC	10000	09/02/89	68	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T11C	*T/W 22	1	SECONDARY	PCC	21667	09/05/89	80	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T14C	*T/W 16	1	SECONDARY	AC	7083	09/05/89	98	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T16C	*T/W 17	1	SECONDARY	PCC	12500	09/02/89	100	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T17C	*T/W 18	1	SECONDARY	AC	7083	09/05/89	46	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T18C	*COMPASS ROSE	1	SECONDARY	PCC	2083	09/06/89	48	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T19A	*ALERT T/W	1	PRIMARY	AC	10000	09/08/89	73	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T20A	*LADDER T/W	1	PRIMARY	PCC	25000	09/03/89	74	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T21A	*T/W 19	1	PRIMARY	AC	36875	09/06/89	48	
BRANCH USE- TAXIWAY		[FROM] -			[TO] -			
T22C	*T/W 24	1	SECONDARY	AC	12167	09/06/89	100	

BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T23C *T/W 3		1	SECONDARY PCC	30000	09/01/89	67	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T24B *POWER CK PAD T/W		1	SECONDARY PCC	889	09/06/89	91	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T26C *T/W 15A		1	SECONDARY AC	4528	09/04/89	79	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T27C *T/W 1		1	SECONDARY AC	12500	09/06/89	100	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T32A *T/W 19		1	PRIMARY PCC	9294	09/06/89	54	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T33A *LADDER T/W		1	PRIMARY AC	9583	09/06/89	64	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T34A *T/W 14		1	PRIMARY PCC	4708	09/02/89	87	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T35A *T/W 14		1	PRIMARY PCC	5375	09/02/89	13	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T36A *LADDER T/W		1	PRIMARY PCC	11250	09/06/89	72	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T40B *PWR CK PAD T/W		1	SECONDARY PCC	1133	09/04/89	91	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T41A *LADDER T/W		1	PRIMARY PCC	11076	09/05/89	72	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
T42C *T/W 3		1	SECONDARY PCC	1542	09/04/89	68	
BRANCH USE-	TAXIWAY	[FROM]-		[TO]-			
A1B *T/W 15 WARMUP		1	SECONDARY PCC	9375	09/02/89	98	
BRANCH USE-	APRON	[FROM]-		[TO]-			
A2B *T/W 15 WARMUP		1	SECONDARY PCC	5556	09/02/89	43	
BRANCH USE-	APRON	[FROM]-		[TO]-			
A3B *OPERATIONAL APRON		1	PRIMARY PCC	17500	09/01/89	65	
BRANCH USE-	APRON	[FROM]-		[TO]-			
A4B *OPERATIONAL APRON		1	PRIMARY PCC	10000	09/01/89	77	
BRANCH USE-	APRON	[FROM]-		[TO]-			
A5B *OPERATIONAL APRON		1	PRIMARY PCC	316956	09/01/89	76	
BRANCH USE-	APRON	[FROM]-		[TO]-			
A6B *OPERATIONAL APRON		1	PRIMARY PCC	64167	09/06/89	69	

BRANCH USE-	APRON	[FROM] -		[TO] -		
A7B *OPERATIONAL	APRON	1	PRIMARY PCC	79722	09/06/89	67
BRANCH USE-	APRON	[FROM] -		[TO] -		
A8B *OPERATIONAL	APRON	1	SECONDARY PCC	5678	09/06/89	47
BRANCH USE-	APRON	[FROM] -		[TO] -		
A9B *WARMUP	APRON	1	SECONDARY AC	14933	09/06/89	21
BRANCH USE-	APRON	[FROM] -		[TO] -		
A10B *WARMUP		1	SECONDARY PCC	15556	09/02/89	55
BRANCH USE-	APRON	[FROM] -		[TO] -		
A11C *CHRISTMAS TREE	APRON	1	SECONDARY PCC	37500	09/05/89	76
BRANCH USE-	APRON	[FROM] -		[TO] -		
A12C *CHRISTMAS TREE	APRON	1	SECONDARY PCC	25000	09/05/89	55
BRANCH USE-	APRON	[FROM] -		[TO] -		
A13B *ALERT	APRON	1	SECONDARY PCC	667	09/05/89	44
BRANCH USE-	APRON	[FROM] -		[TO] -		
A14B *ALERT	APRON	1	SECONDARY PCC	14583	09/05/89	99
BRANCH USE-	APRON	[FROM] -		[TO] -		
A15B *MAINTENANCE	APRON	1	SECONDARY PCC	2500	09/05/89	68
BRANCH USE-	APRON	[FROM] -		[TO] -		
A16B *MAINTENANCE	APRON	1	SECONDARY PCC	3333	09/07/89	60
BRANCH USE-	APRON	[FROM] -		[TO] -		
A17B *MAINTENANCE	APRON	1	SECONDARY AC	24333	09/05/89	64
BRANCH USE-	APRON	[FROM] -		[TO] -		
A18C *COMPASS ROSE		1	SECONDARY PCC	1963	09/05/89	49
BRANCH USE-	APRON	[FROM] -		[TO] -		
A19B *WEST	APRON	1	SECONDARY PCC	68056	09/05/89	65
BRANCH USE-	APRON	[FROM] -		[TO] -		
A21B *WEST	APRON	1	SECONDARY PCC	14208	09/04/89	36
BRANCH USE-	APRON	[FROM] -		[TO] -		
A22B *NORTH	APRON	1	SECONDARY PCC	3333	09/01/89	80
BRANCH USE-	APRON	[FROM] -		[TO] -		
A23B *HARD STAND		1	SECONDARY PCC	089	09/04/89	100
BRANCH USE-	APRON	[FROM] -		[TO] -		
A24B *NORTH	APRON	1	SECONDARY PCC	3958	09/01/89	81
BRANCH USE-	APRON	[FROM] -		[TO] -		
A25B *NORTH	APRON	1	SECONDARY PCC	15611	09/01/89	86
BRANCH USE-	APRON	[FROM] -		[TO] -		

A26B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	19167 [TO] -	09/01/89	67
A28B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	18333 [TO] -	09/04/89	60
A29B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	12222 [TO] -	09/04/89	67
A30B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	24444 [TO] -	09/04/89	71
A33B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	10000 [TO] -	09/01/89	77
A35B *OPERATIONAL APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	30831 [TO] -	09/04/89	
A38B *BLDG APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	2177 [TO] -	09/01/89	43
A39B *BLDG APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	1250 [TO] -	09/03/89	85
A40B *DANGEROUS CARGO PAD BRANCH USE- APRON	1 [FROM] -	SECONDARY AC	51111 [TO] -	09/04/89	89
A45B *APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	4861 [TO] -	09/02/89	88
A47B *HANGAR APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	1111 [TO] -	09/06/89	95
A48B *HANGAR APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	1250 [TO] -	09/04/89	95
A49B *WASHRACK BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	3333 [TO] -	09/04/89	72
A50B *NORTH APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	3958 [TO] -	09/01/89	74
A51B *WEST APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	1667 [TO] -	09/04/89	65
A52B *WEST APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	1667 [TO] -	09/04/89	75
A57B *BLDG APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY PCC	3333 [TO] -	09/04/89	79
A59B *HANGAR APRON BRANCH USE- APRON	1 [FROM] -	SECONDARY AC	8333 [TO] -	09/03/89	66

A60B *HANGAR APRON	1	SECONDARY AC	5556	09/04/89	94
BRANCH USE- APRON	[FROM] -		[TO] -		
A61B *HANGAR APRON	1	SECONDARY AC	83333	09/04/89	75
BRANCH USE- APRON	[FROM] -		[TO] -		
A63B *HANGAR APRON	1	SECONDARY PCC	8888	09/01/89	60
BRANCH USE- APRON	[FROM] -		[TO] -		
A64B *POWER TRIM APRON	1	SECONDARY PCC	1477	09/04/89	
BRANCH USE- APRON					
A65B *POWER TRIM APRON	1	SECONDARY AC	1667	09/04/89	
BRANCH USE- APRON					
A66B *HANGAR APRON	1	SECONDARY PCC	2312	09/04/89	
BRANCH USE- APRON					

INSPECTION SCHEDULE REPORT

AGENCY NAME: DAVIS-MONTHAN AF BASE REPORT DATE: 89/11/02.
 BRANCH USE: MTRPOOL STORAGE ROADWAY PARKING RUNWAY APRON HELIPAD TAXIWAY
 PAVEMENT RANK: P S T X N
 SURFACE TYPE: AC ST PCC GR X BR APC
 ZONE : ALL
 SECTION CATEGORY: A B C D E F G I J K Y N

INSPECTION SCHEDULE TABLE

FY TO	NO. OF SECT.	PAVEMENT RANK				
INSP.	TO INSP.	PRIMARY	SECONDARY	TERTIARY	OTHER	NOT APPLIC
1990	60	37	23	0	0	0
1991	4	3	1	0	0	0
1992	4	3	1	0	0	0
1993	13	6	7	0	0	0
1994	0	0	0	0	0	0
1995	27	8	19	0	0	0

TOTAL NO. OF SECTION: 108
 SECT. NOT NEEDING INSPECTION: 0
 NO. OF MISSING VALUE: 0

INSPECTION SCHEDULE REPORT

AGENCY NAME: DAVIS-MONTHAN AF BASE REPORT DATE: 89/11/02.
 BRANCH USE: MTRPOOL STORAGE ROADWAY PARKING RUNWAY APRON HELIPAD TAXIWAY
 PAVEMENT RANK: P S T X N
 SURFACE TYPE: AC ST PCC GR X BR APC
 ZONE : ALL
 SECTION CATEGORY: A B C D E F G I J K Y N

NO. FY TO
 SEC. INSP.

60	1990	*****
5	1991	*****
5	1992	*****
13	1993	*****
0	1994	
28	1995	*****
108		-----

0 15 30 45 60

NUMBER OF SECTIONS

TOTAL NO. OF SECTION: 108
 SECT. NOT NEEDING INSPECTION: 0
 NO. OF MISSING VALUE: 0

INSPECTION SCHEDULE REPORT

AGENCY NAME: DAVIS-MONTHAN AF BASE REPORT DATE: 89/11/02.

BRANCH USE: MTRPOOL STORAGE ROADWAY PARKING RUNWAY APRON HELIPAD TAXIWAY

PAVEMENT RANK: P S T X N

SURFACE TYPE: AC ST PCC GR X BR APC

ZONE : ALL

SECTION CATEGORY: A B C D E F G I J K Y N

LIST OF CASES IN INSPECTION SCHEDULE REPORT

FY TO INSPECT : 1990		NO. OF SECTIONS : 60		
BRANCH NUMBER	BRANCH USE	SECT. NO.	PAVE. RANK	SUT SEC AREA
A10B	APRON	1	S	PCC 15556
A12B	APRON	1	S	PCC 25000
A13B	APRON	1	S	PCC 667
A15B	APRON	1	S	PCC 2500
A16B	APRON	1	S	PCC 3333
A17B	APRON	1	S	AC 24333
A18B	APRON	1	S	PCC 1963
A19B	APRON	1	S	PCC 68056
A21B	APRON	1	S	PCC 14208
A26B	APRON	1	S	PCC 19167
A28B	APRON	1	S	PCC 18333
A29B	APRON	1	S	PCC 12222
A2B	APRON	1	S	PCC 5556
A38B	APRON	1	S	PCC 2177
A3B	APRON	1	P	PCC 17500
A51B	APRON	1	S	PCC 1667
A59B	APRON	1	S	AC 8333
A63B	APRON	1	S	PCC 8888
A6B	APRON	1	P	PCC 64167
A7B	APRON	1	P	PCC 79722
A8B	APRON	1	S	PCC 5678
A9B	APRON	1	S	AC 14933
R10C	RUNWAY	1	P	AC 8782
R11C	RUNWAY	1	P	PCC 6667
R12C	RUNWAY	1	P	PCC 24333
R13A	RUNWAY	1	P	PCC 11111
R14A	RUNWAY	1	P	PCC 11111
R17C	RUNWAY	1	P	PCC 14000
R19C	RUNWAY	1	P	AC 11111
R1A	RUNWAY	1	P	PCC 6667 0+00

3+00

R21C	RUNWAY	1	P	AC	16667
R22C	RUNWAY	1	P	AC	12222
R23C	RUNWAY	1	P	PCC	444
R25D	RUNWAY	1	P	AC	15156
R26D	RUNWAY	1	P	AC	2222
R27D	RUNWAY	1	P	AC	556
R28D	RUNWAY	1	P	AC	11944
R29D	RUNWAY	1	P	AC	39444
R30C	RUNWAY	1	P	AC	5000
R32D	RUNWAY	1	P	AC	5000
R33D	RUNWAY	1	P	AC	5556
R34D	RUNWAY	1	P	AC	556
R35C	RUNWAY	1	P	AC	2139
R36D	RUNWAY	1	P	AC	17778
R37D	RUNWAY	1	P	AC	3611
R38C	RUNWAY	1	P	AC	3611
R40C	RUNWAY	1	P	AC	20556
R7D	RUNWAY	1	P	AC	8889
R8D	RUNWAY	1	P	AC	1667
T10A	TAXIWAY	1	P	PCC	10000
T17C	TAXIWAY	1	S	AC	7083
T18C	TAXIWAY	1	S	PCC	2083
T19A	TAXIWAY	1	P	AC	10000
T21A	TAXIWAY	1	P	AC	36875
T23C	TAXIWAY	1	S	PCC	30000
T32A	TAXIWAY	1	P	PCC	9294
T33A	TAXIWAY	1	P	AC	9583
T35A	TAXIWAY	1	P	PCC	5375
T41A	TAXIWAY	1	P	PCC	11076
T42C	TAXIWAY	1	S	PCC	1542

FY TO INSPECT : 1991					NO. OF SECTIONS :		
BRANCH	BRANCH	SECT.	PAVE.	SUT	SEC	FROM	TO
NUMBER	USE	NO.	RANK		AREA		
A30B	APRON	1	S	PCC	24444		
A65B	APRON	1	S	AC	1667		
R18C	RUNWAY	1	P	AC	2800		
R31D	RUNWAY	1	P	AC	5000		
R39C	RUNWAY	1	P	AC	3051		

FY TO INSPECT : 1992					NO. OF SECTIONS :		
BRANCH	BRANCH	SECT.	PAVE.	SUT	SEC	FROM	TO
NUMBER	USE	NO.	RANK		AREA		
A49B	APRON	1	S	PCC	3333		
A64B	APRON	1	S	PCC	1477		
R6D	RUNWAY	1	P	AC	10267		
T36A	TAXIWAY	1	P	PCC	11250		
T5A	TAXIWAY	1	P	PCC	25556		

FY TO INSPECT : 1993					NO. OF SECTIONS : 13		TO
BRANCH NUMBER	BRANCH USE	SECT. NO.	PAVE. RANK	SUT SEC	FROM AREA		
A23B	APRON	1	S	PCC	89		
A39B	APRON	1	S	PCC	1250		
A45B	APRON	1	S	PCC	4861		
R15A	RUNWAY	1	P	PCC	4444		
R24C	RUNWAY	1	P	PCC	1111		
T16C	TAXIWAY	1	S	PCC	12500		
T22C	TAXIWAY	1	S	AC	12167		
T24B	TAXIWAY	1	S	PCC	889		
T27C	TAXIWAY	1	S	AC	12500		
T3A	TAXIWAY	1	P	AC	25988		
T4A	TAXIWAY	1	P	AC	18528		
T7A	TAXIWAY	1	P	AC	3990		
T8A	TAXIWAY	1	P	AC	1470		

FY TO INSPECT : 1995					NO. OF SECTIONS : 27		TO
BRANCH NUMBER	BRANCH USE	SECT. NO.	PAVE. RANK	SUT SEC	FROM AREA		
A11C	APRON	1	S	PCC	37500		
A14B	APRON	1	S	PCC	14583		
A1B	APRON	1	S	PCC	9375		
A22B	APRON	1	S	PCC	3333		
A24B	APRON	1	S	PCC	3958		
A25B	APRON	1	S	PCC	15611		
A33B	APRON	1	S	PCC	10000		
A35B	APRON	1	S	PCC	30831		
A40B	APRON	1	S	AC	51111		
A47B	APRON	1	S	PCC	1111		
A48B	APRON	1	S	PCC	1250		
A4B	APRON	1	P	PCC	10000		
A50B	APRON	1	S	PCC	3958		
A52B	APRON	1	S	PCC	1667		
A57B	APRON	1	S	PCC	3333		
A5B	APRON	1	P	PCC	316956		
A60B	APRON	1	S	AC	5556		
A61B	APRON	1	S	AC	83333		
A66B	APRON	1	S	PCC	2312		
R16A	RUNWAY	1	P	PCC	11111		
T11C	TAXIWAY	1	S	PCC	21667		
T14C	TAXIWAY	1	S	AC	7083		
T1A	TAXIWAY	1	P	PCC	5139		
T20A	TAXIWAY	1	P	PCC	25000		
T26C	TAXIWAY	1	S	AC	4528		
T34A	TAXIWAY	1	P	PCC	4708		
T40B	TAXIWAY	1	S	PCC	1133		
T6A	TAXIWAY	1	P	PCC	25556		
T9A	TAXIWAY	1	P	PCC	3780		

TOTAL NO. OF SECTION: 108
 SECT. NOT NEEDING INSPECTION: 0
 NO. OF MISSING VALUE: 0
 MISSING BR NO. SEC. NO.

::

::

MINIMUM PCI TABLE

	P	S	T	X	N
MTRPOOL	70	70	70	70	70
STORAGE	70	70	70	70	70
ROADWAY	70	70	70	70	70
PARKING	70	70	70	70	70
RUNWAY	70	70	70	70	70
APRON	70	70	70	70	70
HELIPAD	70	70	70	70	70
TAXIWAY	70	70	70	70	70

	RATE LIMIT
RATE(PTS/YR)	YRS TO INSP
GT 10	1
6 - 10	1
2 - 5	3
LT 2	5

SAMPCUR - CURRENT INSPECTION RESULTS

AGENCY NUMBER - 1 DAVIS-MONTHAN AF BASE

BRANCH NAME - RUNWAY 12-30 SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - R1A SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 96

INSPECTION DATE - 09/01/89 PCI- 36 RATING- POOR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 4
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 36
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	4.16	2.0
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0
67 LG PATCH/UTIL	HIGH	6 SLABS	25.00	47.2
67 LG PATCH/UTIL	LOW	3 SLABS	12.50	7.0
63 LINEAR CR	LOW	3 SLABS	12.50	10.0
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	13 SLABS	54.16	7.8
66 SMALL PATCH	LOW	2 SLABS	8.33	1.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	4 SLABS	4.16	2.0
65 JT SEAL DAMAGE	MEDIUM	96 SLABS	100.00	7.0
67 LG PATCH/UTIL	HIGH	24 SLABS	25.00	47.2
67 LG PATCH/UTIL	LOW	12 SLABS	12.50	7.0
63 LINEAR CR	LOW	12 SLABS	12.50	10.0
70 SCALING/CRAZING	LOW	96 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	52 SLABS	54.16	7.8
66 SMALL PATCH	LOW	8 SLABS	8.33	1.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 10.10 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 7.07 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 82.83 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 1680 LF
 BRANCH NUMBER - R6D SECTION WIDTH - 54 LF

SECTION NUMBER - 1

SECTION AREA - 10080 SY

INSPECTION DATE - 09/02/89 PCI- 77 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 17
 NUMBER OF SAMPLES SURVEYED- 5
 RECOMMENDED SAMPLES TO BE SURVEYED- 9
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 7.2

SAMPLE UNIT-14 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 85

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	275 LF	5.50	15.0

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 68

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	325 LF	6.50	17.0
48 LONG/TRANS CR	MEDIUM	10 LF	0.20	5.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	240 LF	4.80	13.5
48 LONG/TRANS CR	MEDIUM	20 LF	0.40	7.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-7 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	280 LF	5.60	15.2
48 LONG/TRANS CR	MEDIUM	15 LF	0.30	6.1
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-9 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 84

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	290 LF	5.80	15.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

48 LONG/TRANS CR	LOW	5217 LF	5.64	15.2
48 LONG/TRANS CR	MEDIUM	167 LF	0.18	4.8
52 WEATHER/RAVEL	LOW	55500 SF	60.06	21.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	800 LF
BRANCH NUMBER -	R7C	SECTION WIDTH -	100 LF
SECTION NUMBER -	1	SECTION AREA -	8889 SY

INSPECTION DATE -	09/02/89	PCI-	65	RATING-	GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	16
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	11
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	6.0

SAMPLE UNIT-12 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 65
-------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2000 SF	40.00	26.5
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 71
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	375 LF	7.50	18.9
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-7 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 59
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	37310 SF	46.63	27.8
48 LONG/TRANS CR	LOW	1999 LF	2.49	8.9

52 WEATHER/RAVEL

LOW

79950 SF

99.93

26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	300 LF
BRANCH NUMBER -	R8C	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	1667 SY

INSPECTION DATE -	09/02/89	PCI-	72	RATING-	VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	3
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 72
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	350 LF	7.00	18.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	1050 LF	6.99	17.9
52 WEATHER/RAVEL	LOW	15000 SF	99.98	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	2050 LF
BRANCH NUMBER -	R10C	SECTION WIDTH -	40 LF
SECTION NUMBER -	1	SECTION AREA -	8782 SY

INSPECTION DATE -	09/02/89	PCI-	72	RATING-	VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	20
NUMBER OF SAMPLES SURVEYED-	3

RECOMMENDED SAMPLES TO BE SURVEYED-
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-

5
2.6

SAMPLE UNIT-12 (RANDOM) SAMPLE SIZE- 4000 SF SAMPLE PCI- 73

DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
48 LONG/TRANS CR LOW 240 LF 6.00 16.0
52 WEATHER/RAVEL LOW 4000 SF 100.00 26.4

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 4000 SF SAMPLE PCI- 69

DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
48 LONG/TRANS CR LOW 350 LF 8.75 21.2
52 WEATHER/RAVEL LOW 4000 SF 100.00 26.4

SAMPLE UNIT-7 (RANDOM) SAMPLE SIZE- 4000 SF SAMPLE PCI- 74

DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
48 LONG/TRANS CR LOW 210 LF 5.25 14.5
52 WEATHER/RAVEL LOW 4000 SF 100.00 26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	5272 LF	6.67	17.3
52 WEATHER/RAVEL	LOW	79080 SF	100.05	26.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30 SLAB LENGTH - 25.0 LF
BRANCH NUMBER - R11C SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 96

INSPECTION DATE - 09/03/89 PCI- 58 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 4
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 58
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	2 SLABS	8.33	3.0
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	6 SLABS	25.00	29.8

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	8 SLABS	8.33	3.0
70 SCALING/CRAZING	LOW	96 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	24 SLABS	25.00	29.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	59.84 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	40.16 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	R12C	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	296

INSPECTION DATE -	09/02/89	PCI-	43	RATING-	FAIR
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	14
NUMBER OF SAMPLES SURVEYED-	1
RECOMMENDED SAMPLES TO BE SURVEYED-	14
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	16.2

SAMPLE UNIT-6 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 54
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	LOW	7 SLABS	35.00	18.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	3 SLABS	15.00	22.3
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	9 SLABS	2.57	1.4
65 JT SEAL DAMAGE	MEDIUM	175 SLABS	50.00	7.0
63 LINEAR CR	LOW	61 SLABS	17.42	12.4
70 SCALING/CRAZING	LOW	315 SLABS	90.00	16.0

72 SHATTERED SLAB	LOW	26 SLABS	7.42	14.4
72 SHATTERED SLAB	MEDIUM	88 SLABS	25.14	43.1
73 SHRINKAGE CR	N/A	26 SLABS	7.42	1.2
66 SMALL PATCH	LOW	18 SLABS	5.14	0.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	72.74 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	7.28 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	19.98 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	R13A	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	216

INSPECTION DATE -	09/03/89	PCI-	58	RATING-	GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	8
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	8
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	20.5

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	24 SLABS	SAMPLE PCI-	31
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
70 SCALING/CRAZING	LOW	16 SLABS	80.00	15.2
72 SHATTERED SLAB	MEDIUM	10 SLABS	50.00	60.9
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	2 SLABS	10.00	1.1

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	38
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	3 SLABS	15.00	11.3
63 LINEAR CR	MEDIUM	5 SLABS	25.00	31.8
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
72 SHATTERED SLAB	MEDIUM	2 SLABS	10.00	27.0
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5

SAMPLE UNIT-8 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

66 SMALL PATCH	LOW	2 SLABS	10.00	1.1
----------------	-----	---------	-------	-----

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	53 SLABS	33.12	2.0
63 LINEAR CR	LOW	21 SLABS	13.12	10.3
63 LINEAR CR	MEDIUM	21 SLABS	13.12	22.1
70 SCALING/CRAZING	LOW	160 SLABS	100.00	17.0
72 SHATTERED SLAB	MEDIUM	5 SLABS	3.12	9.9
73 SHRINKAGE CR	N/A	29 SLABS	18.12	2.5
66 SMALL PATCH	LOW	5 SLABS	3.12	0.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	65.89 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	3.12 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	31.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	R14A	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	160

INSPECTION DATE -	09/02/89	PCI-	27	RATING-	POOR
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	8
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 24 SLABS SAMPLE PCI- 27

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	24 SLABS	100.00	2.0
63 LINEAR CR	LOW	5 SLABS	20.83	13.9
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
72 SHATTERED SLAB	MEDIUM	12 SLABS	50.00	60.9
73 SHRINKAGE CR	N/A	2 SLABS	8.33	1.3
66 SMALL PATCH	LOW	4 SLABS	16.66	1.8

 SAMPLE UNIT-4 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 56

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	5 SLABS	25.00	15.5
63 LINEAR CR	MEDIUM	3 SLABS	15.00	24.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	8 SLABS	40.00	5.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	160 SLABS	100.00	2.0
63 LINEAR CR	LOW	33 SLABS	20.62	13.9
70 SCALING/CRAZING	LOW	160 SLABS	100.00	17.0
72 SHATTERED SLAB	MEDIUM	80 SLABS	50.00	60.9
73 SHRINKAGE CR	N/A	13 SLABS	8.12	1.3
66 SMALL PATCH	LOW	27 SLABS	16.87	1.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	77.19 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	2.06 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	20.74 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	R15A	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	64

INSPECTION DATE -	09/02/89	PCI-	77	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	16 SLABS	SAMPLE PCI-	77
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	16 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	16 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	3 SLABS	18.75	2.6
66 SMALL PATCH	LOW	2 SLABS	12.50	1.2

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	64 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	64 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	12 SLABS	18.75	2.6
66 SMALL PATCH	LOW	8 SLABS	12.50	1.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	8.77 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	91.23 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R16A
SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
SLAB WIDTH - 25.0 LF
NUMBER OF SLABS - 160

INSPECTION DATE - 09/02/89 PCI= 84 RATING= VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION= 3
NUMBER OF SAMPLES SURVEYED= 2
RECOMMENDED SAMPLES TO BE SURVEYED= 8
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED= 4.2

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 81

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 87

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	160 SLABS	100.00	7.0
63 LINEAR CR	LOW	4 SLABS	2.50	2.5
70 SCALING/CRAZING	LOW	80 SLABS	50.00	12.2
73 SHRINKAGE CR	N/A	4 SLABS	2.50	0.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES = 11.11 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES = 31.11 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES = 57.78 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R17C
SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
SLAB WIDTH - 25.0 LF
NUMBER OF SLABS - 204

INSPECTION DATE - 09/02/89 PCI= 47 RATING= FAIR
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION= 8
NUMBER OF SAMPLES SURVEYED= 2

RECOMMENDED SAMPLES TO BE SURVEYED-

8

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-

4.9

SAMPLE UNIT-1 (RANDOM)		SAMPLE SIZE- 21 SLABS		SAMPLE PCI- 43
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	21 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	1 SLABS	4.76	2.9
63 LINEAR CR	LOW	7 SLABS	33.33	17.6
63 LINEAR CR	MEDIUM	5 SLABS	23.80	30.9
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0
66 SMALL PATCH	LOW	1 SLABS	4.76	0.6

SAMPLE UNIT-8 (RANDOM)		SAMPLE SIZE- 27 SLABS		SAMPLE PCI- 50
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	27 SLABS	100.00	12.0
63 LINEAR CR	HIGH	1 SLABS	3.70	13.1
63 LINEAR CR	LOW	5 SLABS	18.51	12.9
63 LINEAR CR	MEDIUM	2 SLABS	7.40	15.5
70 SCALING/CRAZING	LOW	27 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	5 SLABS	18.51	2.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	201 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	4 SLABS	1.99	1.4
63 LINEAR CR	HIGH	4 SLABS	1.99	7.9
63 LINEAR CR	LOW	50 SLABS	24.87	15.4
63 LINEAR CR	MEDIUM	29 SLABS	14.42	23.4
70 SCALING/CRAZING	LOW	201 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	21 SLABS	10.44	1.5
66 SMALL PATCH	LOW	4 SLABS	1.99	0.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	59.26 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	15.23 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	25.51 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	1680 LF
BRANCH NUMBER -	R18C	SECTION WIDTH -	15 LF
SECTION NUMBER -	1	SECTION AREA -	2800 SY

INSPECTION DATE -	09/02/89	PCI=	74	RATING=	VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION= 6
 NUMBER OF SAMPLES SURVEYED= 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	100 LF	2.00	8.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	504 LF	2.00	8.0
52 WEATHER/RAVEL	LOW	25200 SF	100.00	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 1000 LF
 BRANCH NUMBER - R19C SECTION WIDTH - 100 LF
 SECTION NUMBER - 1 SECTION AREA - 11111 SY

INSPECTION DATE - 09/02/89 PCI= 73 RATING= VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION= 20
 NUMBER OF SAMPLES SURVEYED= 3
 RECOMMENDED SAMPLES TO BE SURVEYED= 18
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED= 15.5

 SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7

 SAMPLE UNIT-10 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 91

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	135 LF	2.70	9.4

 SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	1500 LF
BRANCH NUMBER -	R21C	SECTION WIDTH -	100 LF
SECTION NUMBER -	1	SECTION AREA -	16667 SY

TOTAL NUMBER OF SAMPLES IN SECTION-	30
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	20
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	8.6

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	285 LF	5.70	15.4
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	50000 SF	33.33	24.8
48 LONG/TRANS CR	LOW	4600 LF	3.06	10.1
52 WEATHER/RAVEL	LOW	150000 SF	99.99	26.4

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

INSPECTION DATE - 09/02/89 PCI- 65 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 62

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2000 SF	40.00	26.5
48 LONG/TRANS CR	LOW	170 LF	3.40	10.7
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-18 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	75 LF	1.50	6.5
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-7 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 59

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	51310 SF	46.64	27.8
48 LONG/TRANS CR	LOW	1796 LF	1.63	6.8
52 WEATHER/RAVEL	LOW	109950 SF	99.95	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SLAB LENGTH -	20.0 LF
BRANCH NUMBER -	R23C	SLAB WIDTH -	20.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	6

INSPECTION DATE -	09/02/89	PCI-	11	RATING-	VERY POOR
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	1
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	9 SLABS	SAMPLE PCI-	11
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	9 SLABS	100.00	7.0
67 LG PATCH/UTIL	HIGH	9 SLABS	100.00	89.0
70 SCALING/CRAZING	LOW	9 SLABS	100.00	17.0
72 SHRINKAGE CR	N/A	2 SLABS	22.22	3.1

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	6 SLABS	100.00	7.0
67 LG PATCH/UTIL	HIGH	6 SLABS	100.00	89.0
70 SCALING/CRAZING	LOW	6 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	1 SLABS	16.66	2.3

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	6.07 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	93.93 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - R24C SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 16

INSPECTION DATE - 09/02/89 PCI- 85 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 24 SLABS SAMPLE PCI- 85

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	2 SLABS	8.33	7.3
63 LINEAR CR	MEDIUM	1 SLABS	4.16	10.2
73 SHRINKAGE CR	N/A	2 SLABS	8.33	1.3

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	6.25	5.9
63 LINEAR CR	MEDIUM	1 SLABS	6.25	13.6
73 SHRINKAGE CR	N/A	1 SLABS	6.25	1.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	94.66 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	5.34 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 2480 LF
 BRANCH NUMBER - R25D SECTION WIDTH - 54 LF
 SECTION NUMBER - 1 SECTION AREA - 14880 SY

INSPECTION DATE - 09/02/89 PCI- 71 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 25
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMENDED SAMPLES TO BE SURVEYED- 5
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 1.0

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 71

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

48 LONG/TRANS CR	LOW	380 LF	7.60	19.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 72
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	325 LF	6.50	17.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-8 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 70
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	410 LF	8.20	20.1
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	10135 LF	7.43	18.7
52 WEATHER/RAVEL	LOW	136350 SF	99.96	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	400 LF
BRANCH NUMBER -	R26D	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	2222 SY

INSPECTION DATE -	09/02/89	PCI-	70	RATING-	GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1

RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 70
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	420 LF	8.40	20.5
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	1680 LF	8.40	20.5
52 WEATHER/RAVEL	LOW	20000 SF	100.01	26.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 100 LF
 BRANCH NUMBER - R27D SECTION WIDTH - 50 LF
 SECTION NUMBER - 1 SECTION AREA - 556 SY

INSPECTION DATE - 09/02/89 PCI- 67 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 67

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	4000 SF	80.00	32.9
48 LONG/TRANS CR	LOW	230 LF	4.60	13.1

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	4000 SF	79.93	32.9
48 LONG/TRANS CR	LOW	230 LF	4.59	13.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 2065 LF

BRANCH NUMBER - R28D
SECTION NUMBER - 1

SECTION WIDTH - 50 LF
SECTION AREA - 11472 SY

INSPECTION DATE - 09/02/89 PCI- 69 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 21
NUMBER OF SAMPLES SURVEYED- 3
RECOMMENDED SAMPLES TO BE SURVEYED- 16
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 8.6

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	285 LF	5.70	15.4
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-20 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 59

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2500 SF	50.00	28.5
48 LONG/TRANS CR	LOW	200 LF	4.00	11.9
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-9 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	285 LF	5.70	15.4
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	17925 SF	16.67	20.0
48 LONG/TRANS CR	LOW	5521 LF	5.13	14.2
52 WEATHER/RAVEL	LOW	107550 SF	100.05	26.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30

SECTION LENGTH - 7100 LF

BRANCH NUMBER - R29D
SECTION NUMBER - 1

SECTION WIDTH - 50 LF
SECTION AREA - 39444 SY

INSPECTION DATE - 09/02/89 PCI- 71 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 71
NUMBER OF SAMPLES SURVEYED- 7
RECOMMENDED SAMPLES TO BE SURVEYED- 13
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 8.1

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 73

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	1000 SF	20.00	21.0
48 LONG/TRANS CR	LOW	450 LF	9.00	21.6

SAMPLE UNIT-12 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 69

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	500 SF	10.00	17.2
48 LONG/TRANS CR	LOW	160 LF	3.20	10.3
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 86

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	260 LF	5.20	14.4

SAMPLE UNIT-44 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 59

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-48 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 70

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	390 LF	7.80	19.4
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

48 LONG/TRANS CR	LOW	250 LF	5.00	14.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-56 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 68
-------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	475 LF	9.50	22.5
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	65910 SF	18.56	20.5
48 LONG/TRANS CR	LOW	20128 LF	5.66	15.3
52 WEATHER/RAVEL	LOW	253500 SF	71.40	23.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	900 LF
BRANCH NUMBER -	R30C	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	5000 SY

INSPECTION DATE -	09/02/89	PCI=	69	RATING=	GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION=	9
NUMBER OF SAMPLES SURVEYED=	2
RECOMMENDED SAMPLES TO BE SURVEYED=	9
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED=	3.5

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 66
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	1000 SF	20.00	21.0
45 DEPRESSION	LOW	10 SF	0.20	0.9
48 LONG/TRANS CR	LOW	130 LF	2.60	9.2
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-7 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 71
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

48 LONG/TRANS CR	LOW	360 LF	7.20	18.3
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	4500 SF	10.00	17.2
45 DEPRESSION	LOW	45 SF	0.10	0.3
48 LONG/TRANS CR	LOW	2205 LF	4.90	13.7
52 WEATHER/RAVEL	LOW	45000 SF	100.00	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	99.48 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.52 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	900 LF
BRANCH NUMBER -	R31C	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	5000 SY

INSPECTION DATE -	09/02/89	PCI-	74	RATING-	VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	9
NUMBER OF SAMPLES SURVEYED-	2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
45 DEPRESSION	LOW	25 SF	0.50	2.5	
48 LONG/TRANS CR	LOW	195 LF	3.90	11.7	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

SAMPLE UNIT-6 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
48 LONG/TRANS CR	LOW	150 LF	3.00	10.0	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
45 DEPRESSION	LOW	113 SF	0.25	1.0

48 LONG/TRANS CR	LOW	1553 LF	3.45	10.8
52 WEATHER/RAVEL	LOW	45000 SF	100.00	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	97.38 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	2.62 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	900 LF
BRANCH NUMBER -	R32D	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	5000 SY

INSPECTION DATE -	09/02/89	PCI-	71	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	9
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	0.7

SAMPLE UNIT-3 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 71
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	360 LF	7.20	18.3
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-8 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 70
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	410 LF	8.20	20.1
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	3465 LF	7.70	19.2
52 WEATHER/RAVEL	LOW	45000 SF	100.00	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R33D
SECTION NUMBER - 1

SECTION LENGTH - 1000 LF
SECTION WIDTH - 50 LF
SECTION AREA - 5556 SY

INSPECTION DATE - 09/02/89 PCI= 65 RATING= GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 10
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED SAMPLES TO BE SURVEYED- 5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 0.7

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 65

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	625 LF	12.50	26.5
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	400 LF	8.00	19.8
48 LONG/TRANS CR	MEDIUM	75 LF	1.50	14.2
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	5125 LF	10.24	23.7
48 LONG/TRANS CR	MEDIUM	375 LF	0.74	9.7
52 WEATHER/RAVEL	LOW	50000 SF	99.99	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 70 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R34D
SECTION NUMBER - 1

SECTION LENGTH - 100 LF
SECTION WIDTH - 50 LF
SECTION AREA - 556 SY

INSPECTION DATE - 09/02/89 PCI= 62 RATING= GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
NUMBER OF SAMPLES SURVEYED- 1

RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 62	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
43 BLOCK CR	LOW	2000 SF	40.00	26.5	
48 LONG/TRANS CR	LOW	140 LF	2.80	9.6	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2000 SF	39.96	26.4
48 LONG/TRANS CR	LOW	140 LF	2.79	9.5
52 WEATHER/RAVEL	LOW	5000 SF	99.92	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	385 LF
BRANCH NUMBER -	R35C	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	2139 SY

INSPECTION DATE - 09/02/89	PCI- 44	RATING- FAIR
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 44	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	19250 SF	99.99	53.9
52 WEATHER/RAVEL	LOW	19250 SF	99.99	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

 BRANCH NAME - RUNWAY 12-30 SECTION LENGTH - 3200 LF
 BRANCH NUMBER - R36D SECTION WIDTH - 50 LF
 SECTION NUMBER - 1 SECTION AREA - 17778 SY

INSPECTION DATE - 09/02/89 PCI- 71 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 32
 NUMBER OF SAMPLES SURVEYED- 4
 RECOMMENDED SAMPLES TO BE SURVEYED- 5
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 2.6

SAMPLE UNIT-11 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 71

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	325 LF	6.50	17.0
48 LONG/TRANS CR	MEDIUM	25 LF	0.50	8.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-15 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 72

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	325 LF	6.50	17.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-27 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 73

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	320 LF	6.40	16.8
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 67

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	520 LF	10.40	23.9
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

48 LONG/TRANS CR	LOW	11920 LF	7.44	18.8
48 LONG/TRANS CR	MEDIUM	200 LF	0.12	4.2
52 WEATHER/RAVEL	LOW	160000 SF	99.99	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	650 LF
BRANCH NUMBER -	R37D	SECTION WIDTH -	50 LF
SECTION NUMBER -	1	SECTION AREA -	3611 SY

INSPECTION DATE -	09/02/89	PCI-	66	RATING-	GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	6
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	4.9

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 62
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	380 LF	7.60	19.0
50 PATCHING	LOW	650 SF	13.00	17.2
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 69
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	450 LF	9.00	21.6
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	2698 LF	8.30	20.3
50 PATCHING	LOW	2113 SF	6.50	11.3
52 WEATHER/RAVEL	LOW	32500 SF	100.00	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R38C
SECTION NUMBER - 1

SECTION LENGTH - 650 LF
SECTION WIDTH - 50 LF
SECTION AREA - 3611 SY

INSPECTION DATE - 09/02/89 PCI- 73 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 6
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED SAMPLES TO BE SURVEYED- 5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 1.4

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 72

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2500 SF	50.00	28.5
48 LONG/TRANS CR	LOW	240 LF	4.80	13.5

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	220 LF	4.40	12.7
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	8125 SF	25.00	22.9
48 LONG/TRANS CR	LOW	1495 LF	4.60	13.1
52 WEATHER/RAVEL	LOW	16250 SF	50.00	20.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - RUNWAY 12-30
BRANCH NUMBER - R39C
SECTION NUMBER - 1

SECTION LENGTH - 1373 LF
SECTION WIDTH - 20 LF
SECTION AREA - 3051 SY

INSPECTION DATE - 09/02/89 PCI- 74 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 13
NUMBER OF SAMPLES SURVEYED- 2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
48 LONG/TRANS CR	LOW	250 LF	5.00	14.0	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
48 LONG/TRANS CR	LOW	250 LF	5.00	14.0	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
48 LONG/TRANS CR	LOW	1375 LF	5.00	14.0	
52 WEATHER/RAVEL	LOW	27500 SF	100.14	26.5	

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	RUNWAY 12-30	SECTION LENGTH -	2650 LF
BRANCH NUMBER -	R40C	SECTION WIDTH -	75 LF
SECTION NUMBER -	1	SECTION AREA -	20556 SY

INSPECTION DATE -	09/02/89	PCI-	65	RATING-	GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	36
NUMBER OF SAMPLES SURVEYED-	4
RECOMMENDED SAMPLES TO BE SURVEYED-	14
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	8.5

SAMPLE UNIT-10 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 57	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
43 BLOCK CR	LOW	2000 SF	40.00	26.5	
48 LONG/TRANS CR	LOW	340 LF	6.80	17.6	
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4	

SAMPLE UNIT-17 (RANDOM)		SAMPLE SIZE- 5000 SF		SAMPLE PCI- 70	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	

48 LONG/TRANS CR	LOW	400 LF	8.00	19.8
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 58
------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	2000 SF	40.00	26.5
48 LONG/TRANS CR	LOW	300 LF	6.00	16.0
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

SAMPLE UNIT-24 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 74
-------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	105 LF	2.10	8.2
52 WEATHER/RAVEL	LOW	5000 SF	100.00	26.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	37000 SF	19.99	20.9
48 LONG/TRANS CR	LOW	10591 LF	5.72	15.4
52 WEATHER/RAVEL	LOW	185000 SF	99.99	26.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 15	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T1A	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 74

INSPECTION DATE - 09/02/89	PCI- 82	RATING- VERY GOOD
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-3 (RANDOM)	SAMPLE SIZE- 23 SLABS	SAMPLE PCI- 82
------------------------	-----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	3 SLABS	13.04	4.3

65 JT SEAL DAMAGE	HIGH	23 SLABS	100.00	12.0
73 SHRINKAGE CR	N/A	10 SLABS	43.47	6.3

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	10 SLABS	13.51	4.4
65 JT SEAL DAMAGE	HIGH	74 SLABS	100.00	12.0
73 SHRINKAGE CR	N/A	32 SLABS	43.24	6.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	53.10 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	46.90 PERCENT DEDUCT VALUES.

BRANCH NAME -	T/W 14	SECTION LENGTH -	8505 LF
BRANCH NUMBER -	T3A	SECTION WIDTH -	27 LF
SECTION NUMBER -	1	SECTION AREA -	25988 SY

INSPECTION DATE -	09/02/89	PCI-	100	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	45
NUMBER OF SAMPLES SURVEYED-	5
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-12 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
-------------------------	----------------------	----------------

NO DISTRESS

SAMPLE UNIT-22 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
-------------------------	----------------------	----------------

NO DISTRESS

SAMPLE UNIT-3 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
------------------------	----------------------	----------------

NO DISTRESS

SAMPLE UNIT-30 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
-------------------------	----------------------	----------------

NO DISTRESS

SAMPLE UNIT-7 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
------------------------	----------------------	----------------

NO DISTRESS

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

 BRANCH NAME - T/W 14 SECTION LENGTH - 11500 LF
 BRANCH NUMBER - T4A SECTION WIDTH - 14 LF
 SECTION NUMBER - 1 SECTION AREA - 18528 SY

INSPECTION DATE - 09/02/89 PCI- 100 RATING- EXCELLENT
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NER OF SAMPLES IN SECTION- 25
 NUMBER OF SAMPLES SURVEYED- 4
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-12 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 SAMPLE UNIT-20 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

 BRANCH NAME - T/W 14 SLAB LENGTH - 20.0 LF
 BRANCH NUMBER - T5A SLAB WIDTH - 20.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 575

INSPECTION DATE - 09/06/89 PCI- 73 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 28
 NUMBER OF SAMPLES SURVEYED- 6
 RECOMMENDED SAMPLES TO BE SURVEYED- 21
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 17.6

 SAMPLE UNIT-15 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 77

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
72 SHATTERED SLAB	LOW	1 SLABS	5.00	10.9
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9
66 SMALL PATCH	LOW	4 SLABS	20.00	2.2

SAMPLE UNIT-18 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 52
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	LOW	2 SLABS	10.00	8.5
63 LINEAR CR	MEDIUM	5 SLABS	25.00	31.8
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	20 SLABS	100.00	14.0

SAMPLE UNIT-19 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 88
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

SAMPLE UNIT-26 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 87
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
63 LINEAR CR	LOW	2 SLABS	10.00	8.5
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 85
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2

SAMPLE UNIT-6 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 50
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
67 LG PATCH/UTIL	MEDIUM	20 SLABS	100.00	50.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	96 SLABS	16.69	2.0
65 JT SEAL DAMAGE	MEDIUM	479 SLABS	83.30	7.0
67 LG PATCH/UTIL	MEDIUM	96 SLABS	16.69	21.4
63 LINEAR CR	LOW	19 SLABS	3.30	3.3
63 LINEAR CR	MEDIUM	24 SLABS	4.17	10.2
70 SCALING/CRAZING	LOW	120 SLABS	20.86	7.2
72 SHATTERED SLAB	LOW	5 SLABS	0.86	2.1
73 SHRINKAGE CR	N/A	134 SLABS	23.30	3.2

66 SMALL PATCH LOW 24 SLABS 4.17 0.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 27.42 PERCENT DEDUCT VALUES.

CLIMATE/DURABILITY RELATED DISTRESSES - 15.82 PERCENT DEDUCT VALUES.

OTHER RELATED DISTRESSES - 56.77 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 14	SLAB LENGTH - 20.0 LF
BRANCH NUMBER - T6A	SLAB WIDTH - 20.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 575

INSPECTION DATE - 09/06/89 PCI- 87 RATING- EXCELLENT
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 28
 NUMBER OF SAMPLES SURVEYED- 6
 RECOMMENDED SAMPLES TO BE SURVEYED- 5
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 3.1

SAMPLE UNIT-11 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 85

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2

SAMPLE UNIT-15 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 86

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9

SAMPLE UNIT-23 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 85

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2

SAMPLE UNIT-28 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 85

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2

SAMPLE UNIT-53 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 86

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 93

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	96 SLABS	16.69	2.0
65 JT SEAL DAMAGE	MEDIUM	479 SLABS	83.30	7.0
70 SCALING/CRAZING	LOW	216 SLABS	37.56	10.5
73 SHRINKAGE CR	N/A	19 SLABS	3.30	0.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	44.12 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	55.88 PERCENT DEDUCT VALUES.

BRANCH NAME	T/W 14	SECTION LENGTH -	945 LF
BRANCH NUMBER -	T7A	SECTION WIDTH -	38 LF
SECTION NUMBER -	1	SECTION AREA -	3990 SY

INSPECTION DATE - 09/06/89	PCI- 100	RATING- EXCELLENT
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	8
NUMBER OF SAMPLES SURVEYED-	2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
------------------------	----------------------	----------------

NO DISTRESS

SAMPLE UNIT-6 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI-100
------------------------	----------------------	----------------

NO DISTRESS

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

BRANCH NAME -	T/W 14	SECTION LENGTH -	945 LF
BRANCH NUMBER -	T8A	SECTION WIDTH -	14 LF

SECTION NUMBER - 1

SECTION AREA - 1470 SY

INSPECTION DATE - 09/06/89 PCI- 100 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 3
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

BRANCH NAME - T/W 14 SLAB LENGTH - 20.0 LF
BRANCH NUMBER - T9A SLAB WIDTH - 20.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 85

INSPECTION DATE - 09/07/89 PCI- 97 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 5
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED SAMPLES TO BE SURVEYED- 5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 0.7

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 96

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 16 SLABS SAMPLE PCI- 97

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
73 SHRINKAGE CR	N/A	21 SLABS	24.70	3.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 20
 BRANCH NUMBER - T10A
 SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
 SLAB WIDTH - 25.0 LF
 NUMBER OF SLABS - 144

INSPECTION DATE - 09/02/89 PCI- 68 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 7
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMENDED SAMPLES TO BE SURVEYED- 7
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 11.1

SAMPLE UNIT-4 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 66

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
67 LG PATCH/UTIL	LOW	2 SLABS	10.00	6.0
63 LINEAR CR	LOW	6 SLABS	30.00	17.0
70 SCALING/CRAZING	LOW	9 SLABS	45.00	11.7
70 SCALING/CRAZING	MEDIUM	1 SLABS	5.00	6.9
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 80

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
70 SCALING/CRAZING	LOW	1 SLABS	5.00	2.1
73 SHRINKAGE CR	N/A	5 SLABS	25.00	3.5

SAMPLE UNIT-7 (RANDOM) SAMPLE SIZE- 15 SLABS SAMPLE PCI- 58

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	6.66	2.6
74 JOINT SPALLING	MEDIUM	1 SLABS	6.66	5.7
65 JT SEAL DAMAGE	HIGH	15 SLABS	100.00	12.0
63 LINEAR CR	LOW	5 SLABS	33.33	17.6
70 SCALING/CRAZING	LOW	8 SLABS	53.33	12.6
73 SHRINKAGE CR	N/A	11 SLABS	73.33	11.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	5 SLABS	3.47	1.8
74 JOINT SPALLING	MEDIUM	3 SLABS	2.08	2.1
65 JT SEAL DAMAGE	HIGH	92 SLABS	63.88	12.0
65 JT SEAL DAMAGE	MEDIUM	52 SLABS	36.11	7.0
67 LG PATCH/UTIL	LOW	5 SLABS	3.47	2.2
63 LINEAR CR	LOW	29 SLABS	20.13	13.7
70 SCALING/CRAZING	LOW	47 SLABS	32.63	9.7
70 SCALING/CRAZING	MEDIUM	3 SLABS	2.08	3.1

73 SHRINKAGE CR N/A 47 SLABS 32.63 4.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 24.38 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 33.81 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 41.81 PERCENT DEDUCT VALUES.

 BRANCH NAME - T/W 22 SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - T11C SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 312

INSPECTION DATE - 09/05/89 PCI- 80 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 25
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMENDED SAMPLES TO BE SURVEYED- 11
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 6.9

 SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 18 SLABS SAMPLE PCI- 76

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	5.55	2.1
74 JOINT SPALLING	LOW	1 SLABS	5.55	2.3
65 JT SEAL DAMAGE	MEDIUM	18 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	18 SLABS	100.00	17.0
66 SMALL PATCH	LOW	1 SLABS	5.55	0.7

SAMPLE UNIT-14 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 88

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	4.76	1.8
74 JOINT SPALLING	LOW	1 SLABS	4.76	2.1
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	3 SLABS	14.28	5.3

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 76

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	21 SLABS	100.00	2.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	4.76	10.6
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	10 SLABS	3.20	1.1
74 JOINT SPALLING	LOW	10 SLABS	3.20	1.7

65 JT SEAL DAMAGE	LOW	109 SLABS	34.93	2.0
67 LG PATCH/UTIL	MEDIUM	5 SLABS	1.60	4.0
70 SCALING/CRAZING	LOW	218 SLABS	69.87	14.4
66 SMALL PATCH	LOW	5 SLABS	1.60	0.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	29.61 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	70.39 PERCENT DEDUCT VALUES.

BRANCH NAME -	T/W 16	SECTION LENGTH -	850 LF
BRANCH NUMBER -	T14C	SECTION WIDTH -	75 LF
SECTION NUMBER -	1	SECTION AREA -	7083 SY

INSPECTION DATE -	09/05/89	PCI-	98	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	9
NUMBER OF SAMPLES SURVEYED-	2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE-	5000 SF	SAMPLE PCI-	98
------------------------	--------------	---------	-------------	----

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
49 OIL SPILLAGE	N/A	10 SF	0.20	2.0

SAMPLE UNIT-6 (RANDOM)	SAMPLE SIZE-	5000 SF	SAMPLE PCI-	98
------------------------	--------------	---------	-------------	----

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
49 OIL SPILLAGE	N/A	23 SF	0.46	2.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
49 OIL SPILLAGE	N/A	210 SF	0.32	2.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.

BRANCH NAME -	T/W 17	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	T16C	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	210

INSPECTION DATE -	09/02/89	PCI-	100	RATING-	EXCELLENT
-------------------	----------	------	-----	---------	-----------

CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 11
NUMBER OF SAMPLES SURVEYED- 3
RECOMMENDED SAMPLES TO BE SURVEYED- 5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 0.5

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI-100

NO DISTRESS

SAMPLE UNIT-4 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 99

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI-100

NO DISTRESS

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
66 SMALL PATCH	LOW	4 SLABS	1.90	0.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 18 SECTION LENGTH - 850 LF
BRANCH NUMBER - T17C SECTION WIDTH - 75 LF
SECTION NUMBER - 1 SECTION AREA - 7083 SY

INSPECTION DATE - 09/05/89 PCI- 46 RATING- FAIR
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 11
NUMBER OF SAMPLES SURVEYED- 2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 46

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 46

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	63700 SF	99.92	53.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - COMPASS ROSE	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T18C	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 30

INSPECTION DATE - 09/06/89	PCI- 48	RATING- FAIR
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 15 SLABS SAMPLE PCI- 48

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	15 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	3 SLABS	20.00	10.0
63 LINEAR CR	LOW	14 SLABS	93.33	22.0
63 LINEAR CR	MEDIUM	1 SLABS	6.66	14.2
70 SCALING/CRAZING	LOW	15 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	1 SLABS	6.66	1.1

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	6 SLABS	20.00	10.0
63 LINEAR CR	LOW	28 SLABS	93.33	22.0
63 LINEAR CR	MEDIUM	2 SLABS	6.66	14.2
70 SCALING/CRAZING	LOW	30 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	2 SLABS	6.66	1.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	47.44 PERCENT DEDUCT VALUES.
------	----------------------	------------------------------

CLIMATE/DURABILITY RELATED DISTRESSES - 15.73 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - 36.83 PERCENT DEDUCT VALUES.

BRANCH NAME - ALERT T/W SECTION LENGTH - 1200 LF
BRANCH NUMBER - T19A SECTION WIDTH - 75 LF
SECTION NUMBER - 1 SECTION AREA - 10000 SY

INSPECTION DATE - 09/08/89 PCI- 73 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 24
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED SAMPLES TO BE SURVEYED- 9
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 2.1

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 71

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	735 LF	14.70	29.1

SAMPLE UNIT-9 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	625 LF	12.50	26.5

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	12240 LF	13.60	27.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - LADDER T/W SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T20A SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 360

INSPECTION DATE - 09/03/89 PCI- 74 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 15
NUMBER OF SAMPLES SURVEYED- 3
RECOMMENDED SAMPLES TO BE SURVEYED- 14
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 8.0

SAMPLE UNIT-14 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 67	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	1 SLABS	5.00	4.0	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
63 LINEAR CR	LOW	6 SLABS	30.00	17.0	
70 SCALING/CRAZING	LOW	4 SLABS	20.00	7.0	
73 SHRINKAGE CR	N/A	6 SLABS	30.00	4.2	
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 83	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
63 LINEAR CR	LOW	1 SLABS	5.00	4.9	
70 SCALING/CRAZING	LOW	1 SLABS	5.00	2.1	
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9	

SAMPLE UNIT-8 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 73	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	1 SLABS	5.00	4.0	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
63 LINEAR CR	LOW	3 SLABS	15.00	11.3	
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0	
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5	
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	12 SLABS	3.33	2.4	
65 JT SEAL DAMAGE	HIGH	240 SLABS	66.66	12.0	
65 JT SEAL DAMAGE	MEDIUM	120 SLABS	33.33	7.0	
63 LINEAR CR	LOW	60 SLABS	16.66	12.1	
70 SCALING/CRAZING	LOW	42 SLABS	11.66	4.5	
73 SHRINKAGE CR	N/A	72 SLABS	20.00	2.9	
66 SMALL PATCH	LOW	12 SLABS	3.33	0.4	

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES =	35.11 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES =	46.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES =	18.89 PERCENT DEDUCT VALUES.

BRANCH NAME -	T/W 19	SECTION LENGTH -	4425 LF
BRANCH NUMBER -	T21A	SECTION WIDTH -	75 LF

SECTION NUMBER - 1

SECTION AREA - 36875 SF

INSPECTION DATE - 09/06/89 PCI- 48 RATING- FAIR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 66
 NUMBER OF SAMPLES SURVEYED- 4
 RECOMMENDED SAMPLES TO BE SURVEYED- 8
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 4.5

SAMPLE UNIT-13 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 46

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9

SAMPLE UNIT-21 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 46

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9

SAMPLE UNIT-34 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 55

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	1500 SF	30.00	33.8
48 LONG/TRANS CR	LOW	435 LF	8.70	21.1
48 LONG/TRANS CR	MEDIUM	120 LF	2.40	17.6

SAMPLE UNIT-43 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 46

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	5000 SF	100.00	53.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	MEDIUM	273735 SF	82.48	49.2
48 LONG/TRANS CR	LOW	7217 LF	2.17	8.3
48 LONG/TRANS CR	MEDIUM	1991 LF	0.59	8.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 24
 BRANCH NUMBER - T22C

SECTION LENGTH - 730 LF
 SECTION WIDTH - 150 LF

SECTION NUMBER - 1

SECTION AREA - 12167 SY

INSPECTION DATE - 09/06/89 PCI- 100 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 8
NUMBER OF SAMPLES SURVEYED- 2
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

BRANCH NAME - T/W 3 SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T23C SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 432

INSPECTION DATE - 09/01/89 PCI- 67 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 32
NUMBER OF SAMPLES SURVEYED- 3
RECOMMENDED SAMPLES TO BE SURVEYED- 18
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 9.2

SAMPLE UNIT-11 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 63

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	21 SLABS	100.00	12.0
63 LINEAR CR	LOW	5 SLABS	23.80	15.0
63 LINEAR CR	MEDIUM	1 SLABS	4.76	11.2
73 SHRINKAGE CR	N/A	19 SLABS	90.47	13.1
66 SMALL PATCH	LOW	2 SLABS	9.52	1.0

SAMPLE UNIT-24 (RANDOM) SAMPLE SIZE- 28 SLABS SAMPLE PCI- 78

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	28 SLABS	100.00	7.0
63 LINEAR CR	LOW	3 SLABS	10.71	8.9
73 SHRINKAGE CR	N/A	28 SLABS	100.00	14.0

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 61

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	21 SLABS	100.00	12.0
63 LINEAR CR	LOW	13 SLABS	61.90	21.4
72 SHATTERED SLAB	LOW	1 SLABS	4.76	10.5
73 SHRINKAGE CR	N/A	17 SLABS	80.95	12.1

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	259 SLABS	59.95	12.0
65 JT SEAL DAMAGE	MEDIUM	173 SLABS	40.04	7.0
63 LINEAR CR	LOW	130 SLABS	30.09	17.0
63 LINEAR CR	MEDIUM	6 SLABS	1.38	3.4
72 SHATTERED SLAB	LOW	6 SLABS	1.38	3.4
73 SHRINKAGE CR	N/A	395 SLABS	91.43	13.3
66 SMALL PATCH	LOW	12 SLABS	2.77	0.3

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	42.20 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	33.69 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	24.11 PERCENT DEDUCT VALUES.

BRANCH NAME -	POWER CK PAD T/W	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	T24B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	20

INSPECTION DATE -	09/06/89	PCI-	91	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	1
NUMBER OF SAMPLES SURVEYED-	1

RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	91
------------------------	--------------	----------	-------------	----

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	5 SLABS	25.00	3.5
66 SMALL PATCH	LOW	2 SLABS	10.00	1.1

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	8.33	7.3
73 SHRINKAGE CR	N/A	3 SLABS	25.00	3.5

66 SMALL PATCH

LOW

1 SLABS

8.33

1.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 61.86 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 38.14 PERCENT DEDUCT VALUES.

 BRANCH NAME - T/W 15A SECTION LENGTH - 815 LF
 BRANCH NUMBER - T26C SECTION WIDTH - 50 LF
 SECTION NUMBER - 1 SECTION AREA - 4528 SY

INSPECTION DATE - 09/04/89 PCI- 79 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 8
 NUMBER OF SAMPLES SURVEYED- 2
 RECOMMENDED SAMPLES TO BE SURVEYED- 8
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 19.7

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 65
 DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
 50 PATCHING LOW 550 SF 11.00 15.4
 53 RUTTING MEDIUM 200 SF 4.00 34.8

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 93
 DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
 50 PATCHING LOW 150 SF 3.00 7.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
 50 PATCHING LOW 2856 SF 7.00 11.9
 53 RUTTING MEDIUM 816 SF 2.00 29.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 70.90 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 29.10 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

 BRANCH NAME - T/W 1 SECTION LENGTH - 1500 LF
 BRANCH NUMBER - T27C SECTION WIDTH - 75 LF
 SECTION NUMBER - 1 SECTION AREA - 12500 SY

INSPECTION DATE - 09/06/89 PCI- 100 RATING- EXCELLENT
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 15
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-12 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI-100

NO DISTRESS

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

 BRANCH NAME - T/W 19 SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - T32A SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 133

INSPECTION DATE - 09/06/89 PCI- 54 RATING- FAIR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 9
 NUMBER OF SAMPLES SURVEYED- 2
 RECOMMENDED SAMPLES TO BE SURVEYED- 6
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 4.2

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 57

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	21 SLABS	100.00	12.0
63 LINEAR CR	LOW	2 SLABS	9.52	8.1
63 LINEAR CR	MEDIUM	2 SLABS	9.52	18.4
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	4 SLABS	19.04	2.7
66 SMALL PATCH	LOW	6 SLABS	28.57	3.7

 SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 18 SLABS SAMPLE PCI- 51

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	2 SLABS	11.11	3.7
65 JT SEAL DAMAGE	HIGH	18 SLABS	100.00	12.0
63 LINEAR CR	LOW	3 SLABS	16.66	12.1
63 LINEAR CR	MEDIUM	2 SLABS	11.11	20.1

70 SCALING/CRAZING	LOW	18 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	6 SLABS	33.33	4.7

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	7 SLABS	5.26	2.3
65 JT SEAL DAMAGE	HIGH	133 SLABS	100.00	12.0
63 LINEAR CR	LOW	17 SLABS	12.78	10.1
63 LINEAR CR	MEDIUM	14 SLABS	10.52	19.5
70 SCALING/CRAZING	LOW	133 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	34 SLABS	25.56	3.5
66 SMALL PATCH	LOW	20 SLABS	15.03	1.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	44.85 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	18.18 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	36.97 PERCENT DEDUCT VALUES.

 BRANCH NAME - LADDER T/W SECTION LENGTH - 750 LF
 BRANCH NUMBER - T33A SECTION WIDTH - 115 LF
 SECTION NUMBER - 1 SECTION AREA - 9583 SY

INSPECTION DATE - 09/06/89 PCI= 64 RATING= GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 15
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-14 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7

 SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	LOW	5000 SF	100.00	35.7

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

43 BLOCK CR LOW 86250 SF 100.00 35.7

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 14 SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T34A SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 67

INSPECTION DATE - 09/02/89 PCI- 87 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 4
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 87

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	6.66	6.2
70 SCALING/CRAZING	LOW	3 SLABS	20.00	7.0
73 SHRINKAGE CR	N/A	4 SLABS	26.66	3.7

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	4 SLABS	5.97	5.7
70 SCALING/CRAZING	LOW	13 SLABS	19.40	6.8
73 SHRINKAGE CR	N/A	18 SLABS	26.86	3.7

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 35.19 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - 64.81 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 14 SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T35A SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 77

INSPECTION DATE - 09/02/89 PCI- 13 RATING- VERY POOR
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 5

NUMBER OF SAMPLES SURVEYED-
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

1

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 13	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	MEDIUM	3 SLABS	37.50	39.2
70 SCALING/CRAZING	LOW	5 SLABS	62.50	13.7
72 SHATTERED SLAB	MEDIUM	6 SLABS	75.00	73.5
73 SHRINKAGE CR	N/A	5 SLABS	62.50	9.5
66 SMALL PATCH	LOW	1 SLABS	12.50	1.2

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	MEDIUM	29 SLABS	37.66	39.3
70 SCALING/CRAZING	LOW	48 SLABS	62.33	13.7
72 SHATTERED SLAB	MEDIUM	58 SLABS	75.32	73.6
73 SHRINKAGE CR	N/A	48 SLABS	62.33	9.4
66 SMALL PATCH	LOW	10 SLABS	12.98	1.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 82.29 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - 17.71 PERCENT DEDUCT VALUES.

BRANCH NAME - LADDER T/W SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T36A SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 162

INSPECTION DATE - 09/06/89 PCI- 72 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 12
NUMBER OF SAMPLES SURVEYED- 3
RECOMMENDED SAMPLES TO BE SURVEYED- 6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 5.1

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 71	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	17 SLABS	SAMPLE PCI- 78
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	17 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	17 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	3 SLABS	17.64	2.4
66 SMALL PATCH	LOW	2 SLABS	11.76	1.2

SAMPLE UNIT-8 (RANDOM)		SAMPLE SIZE-	19 SLABS	SAMPLE PCI- 68
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	19 SLABS	100.00	7.0
63 LINEAR CR	MEDIUM	1 SLABS	5.26	12.0
70 SCALING/CRAZING	LOW	19 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	7 SLABS	36.84	5.3
66 SMALL PATCH	LOW	1 SLABS	5.26	0.6
66 SMALL PATCH	MEDIUM	2 SLABS	10.52	5.7

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	162 SLABS	100.00	7.0
63 LINEAR CR	MEDIUM	6 SLABS	3.70	9.2
70 SCALING/CRAZING	LOW	162 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	40 SLABS	24.69	3.4
66 SMALL PATCH	LOW	9 SLABS	5.55	0.7
66 SMALL PATCH	MEDIUM	6 SLABS	3.70	2.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	23.41 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	17.81 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	58.78 PERCENT DEDUCT VALUES.

BRANCH NAME -	PWR CK PAD T/W	SLAB LENGTH -	17.0 LF
BRANCH NUMBER -	T40B	SLAB WIDTH -	17.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	35

INSPECTION DATE -	09/04/89	PCI-	91	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	12 SLABS	SAMPLE PCI- 91
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE

66 SMALL PATCH	HIGH	1 SLABS	8.33	9.2
----------------	------	---------	------	-----

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
66 SMALL PATCH	HIGH	3 SLABS	8.57	9.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.

BRANCH NAME - LADDER T/W	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T41A	SLAB WIDTH - 27.5 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 145

INSPECTION DATE - 09/05/89	PCI- 72	RATING- VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	13
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	18
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	16.8

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	7 SLABS	SAMPLE PCI- 85	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	14.28	10.9
73 SHRINKAGE CR	N/A	2 SLABS	28.57	3.9

SAMPLE UNIT-10 (RANDOM)	SAMPLE SIZE-	7 SLABS	SAMPLE PCI- 78	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	2 SLABS	28.57	16.5
73 SHRINKAGE CR	N/A	5 SLABS	71.42	10.8

SAMPLE UNIT-5 (RANDOM)	SAMPLE SIZE-	7 SLABS	SAMPLE PCI- 53	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	14.28	4.5
65 JT SEAL DAMAGE	MEDIUM	7 SLABS	100.00	7.0
63 LINEAR CR	LOW	1 SLABS	14.28	10.9
72 SHATTERED SLAB	LOW	3 SLABS	42.85	38.9
66 SMALL PATCH	LOW	1 SLABS	14.28	1.5

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	7 SLABS	4.82	2.2
65 JT SEAL DAMAGE	MEDIUM	48 SLABS	33.10	7.0
63 LINEAR CR	LOW	28 SLABS	19.31	13.3
72 SHATTERED SLAB	LOW	21 SLABS	14.48	21.8
73 SHRINKAGE CR	N/A	48 SLABS	33.10	4.6
66 SMALL PATCH	LOW	7 SLABS	4.82	0.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	70.91 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	14.14 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	14.95 PERCENT DEDUCT VALUES.

BRANCH NAME - T/W 3	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - T42C	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 22

INSPECTION DATE - 09/04/89	PCI- 68	RATING- GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	7
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	7
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	12.0

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 69
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT DEDUCT-VALUE
64 DURABILITY CR	LOW	2 SLABS	8.33 2.8
74 JOINT SPALLING	LOW	10 SLABS	41.66 9.7
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00 7.0
63 LINEAR CR	LOW	1 SLABS	4.16 4.1
70 SCALING/CRAZING	LOW	24 SLABS	100.00 17.0
73 SHRINKAGE CR	N/A	1 SLABS	4.16 1.0

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 55
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00 4.5
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00 12.0
63 LINEAR CR	LOW	6 SLABS	30.00 17.0
63 LINEAR CR	MEDIUM	2 SLABS	10.00 19.0
70 SCALING/CRAZING	LOW	2 SLABS	10.00 4.0
73 SHRINKAGE CR	N/A	10 SLABS	50.00 7.4

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE-	30 SLABS	SAMPLE PCI- 79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT DEDUCT-VALUE

65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0
73 SHRINKAGE CR	N/A	30 SLABS	100.00	14.0

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
64 DURABILITY CR	LOW	1 SLABS	4.54	1.6
74 JOINT SPALLING	LOW	3 SLABS	13.63	4.4
65 JT SEAL DAMAGE	HIGH	15 SLABS	68.18	12.0
65 JT SEAL DAMAGE	MEDIUM	7 SLABS	31.81	7.0
63 LINEAR CR	LOW	2 SLABS	9.09	7.8
63 LINEAR CR	MEDIUM	1 SLABS	4.54	10.8
70 SCALING/CRAZING	LOW	8 SLABS	36.36	10.3
73 SHRINKAGE CR	N/A	12 SLABS	54.54	7.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	30.10 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	33.33 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	36.57 PERCENT DEDUCT VALUES.

BRANCH NAME -	T/W 15 WARMUP	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A1B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	135

INSPECTION DATE -	09/02/89	PCI-	98	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	6
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	3.5

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 25 SLABS SAMPLE PCI- 95

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	3 SLABS	12.00	4.0
66 SMALL PATCH	LOW	3 SLABS	12.00	1.2

 SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 25 SLABS SAMPLE PCI-100

NO DISTRESS

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	8 SLABS	5.92	2.4
66 SMALL PATCH	LOW	8 SLABS	5.92	0.7

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.

 BRANCH NAME - T/W 15 WARMUP SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A2B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 80

INSPECTION DATE - 09/02/89 PCI- 43 RATING- FAIR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 4
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 43

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	5 SLABS	25.00	16.0
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	HIGH	1 SLABS	5.00	17.7
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
67 LG PATCH/UTIL	MEDIUM	4 SLABS	20.00	23.7
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	20 SLABS	25.00	16.0
65 JT SEAL DAMAGE	HIGH	80 SLABS	100.00	12.0
67 LG PATCH/UTIL	HIGH	4 SLABS	5.00	17.7
67 LG PATCH/UTIL	LOW	4 SLABS	5.00	3.1
67 LG PATCH/UTIL	MEDIUM	16 SLABS	20.00	23.7
63 LINEAR CR	LOW	4 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	16 SLABS	20.00	2.9
66 SMALL PATCH	LOW	4 SLABS	5.00	0.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 6.06 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 14.83 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 79.11 PERCENT DEDUCT VALUES.

 BRANCH NAME - OPERATIONAL APRON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A3B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 252

INSPECTION DATE - 09/01/89 PCI= 65 RATING= GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION= 13
 NUMBER OF SAMPLES SURVEYED= 4
 RECOMMENDED SAMPLES TO BE SURVEYED= 10
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED= 10.5

SAMPLE UNIT-11 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 79

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	1 SLABS	5.00	4.0
62 CORNER BR	MEDIUM	1 SLABS	5.00	8.2
63 LINEAR CR	LOW	4 SLABS	20.00	13.7
72 SHATTERED SLAB	LOW	0 SLABS	0.00	0.0

SAMPLE UNIT-5 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 61

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	2 SLABS	10.00	3.5
63 LINEAR CR	MEDIUM	4 SLABS	20.00	28.2
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0
70 SCALING/CRAZING	MEDIUM	1 SLABS	5.00	6.9
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	3 SLABS	15.00	1.6

SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 67

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
67 LG PATCH/UTIL	LOW	2 SLABS	10.00	6.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	5.00	11.0
70 SCALING/CRAZING	LOW	7 SLABS	35.00	10.1
72 SHATTERED SLAB	LOW	2 SLABS	10.00	17.8
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	3 SLABS	15.00	1.6

SAMPLE UNIT-9 (RANDOM) SAMPLE SIZE- 16 SLABS SAMPLE PCI- 54

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	16 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	2 SLABS	12.50	7.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	6.25	12.8
63 LINEAR CR	LOW	1 SLABS	6.25	5.9
63 LINEAR CR	MEDIUM	3 SLABS	18.75	27.2
70 SCALING/CRAZING	LOW	6 SLABS	37.50	10.5
73 SHRINKAGE CR	N/A	2 SLABS	12.50	1.8

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	3 SLABS	1.19	0.8
62 CORNER BR	MEDIUM	3 SLABS	1.19	2.0
74 JOINT SPALLING	LOW	7 SLABS	2.77	1.5
65 JT SEAL DAMAGE	LOW	53 SLABS	21.03	2.0
67 LG PATCH/UTIL	LOW	13 SLABS	5.15	3.2
67 LG PATCH/UTIL	MEDIUM	7 SLABS	2.77	6.7
63 LINEAR CR	LOW	17 SLABS	6.74	6.2
63 LINEAR CR	MEDIUM	23 SLABS	9.12	17.9
70 SCALING/CRAZING	LOW	50 SLABS	19.84	6.9
70 SCALING/CRAZING	MEDIUM	3 SLABS	1.19	1.7
72 SHATTERED SLAB	LOW	7 SLABS	2.77	6.6
73 SHRINKAGE CR	N/A	23 SLABS	9.12	1.4
66 SMALL PATCH	LOW	20 SLABS	7.93	0.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	57.96 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	3.46 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	38.58 PERCENT DEDUCT VALUES.

 BRANCH NAME - OPERATIONAL APRON SLAB LENGTH - 15.0 LF
 BRANCH NUMBER - A4B SLAB WIDTH - 12.5 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 480

INSPECTION DATE - 09/01/89 PCI- 77 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	24
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	8
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	3.7

 SAMPLE UNIT-10 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 80

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6
70 SCALING/CRAZING	LOW	3 SLABS	15.00	5.6
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	3 SLABS	15.00	1.6

 SAMPLE UNIT-18 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 73

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
67 LG PATCH/UTIL	LOW	11 SLABS	55.00	19.0
73 SHRINKAGE CR	N/A	13 SLABS	65.00	10.0

SAMPLE UNIT-5 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 79
------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	1 SLABS	5.00	4.0
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0
73 SHRINKAGE CR	N/A	7 SLABS	35.00	5.0
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	8 SLABS	1.66	1.2
75 CORNER SPALLING	LOW	8 SLABS	1.66	0.5
65 JT SEAL DAMAGE	MEDIUM	320 SLABS	66.66	7.0
67 LG PATCH/UTIL	LOW	96 SLABS	20.00	10.0
63 LINEAR CR	MEDIUM	8 SLABS	1.66	4.1
70 SCALING/CRAZING	LOW	40 SLABS	8.33	3.2
73 SHRINKAGE CR	N/A	176 SLABS	36.66	5.2
66 SMALL PATCH	LOW	32 SLABS	6.66	0.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	16.56 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	21.88 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	61.56 PERCENT DEDUCT VALUES.

BRANCH NAME -	OPERATIONAL APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A5B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	4564

INSPECTION DATE -	09/01/89	PCI-	76	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	243
NUMBER OF SAMPLES SURVEYED-	22
RECOMMENDED SAMPLES TO BE SURVEYED-	7
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	6.2

SAMPLE UNIT-105(RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 74
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	3 SLABS	15.00	8.0
70 SCALING/CRAZING	LOW	18 SLABS	90.00	16.0

73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	7 SLABS	35.00	5.0

SAMPLE UNIT-127(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 78
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
70 SCALING/CRAZING	LOW	8 SLABS	40.00	11.0
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	6 SLABS	30.00	4.0

SAMPLE UNIT-133(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 80
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	2 SLABS	10.00	3.5
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9
66 SMALL PATCH	LOW	5 SLABS	25.00	3.2

SAMPLE UNIT-155(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 78
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
70 SCALING/CRAZING	LOW	9 SLABS	45.00	11.7
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	6 SLABS	30.00	4.0

SAMPLE UNIT-161(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 78
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00	4.5
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	7 SLABS	35.00	10.1
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	5 SLABS	25.00	3.2

SAMPLE UNIT-176(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 84
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	15 SLABS	75.00	9.0

SAMPLE UNIT-182(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 79

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
74 JOINT SPALLING	LOW	12 SLABS	60.00	12.1
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9
66 SMALL PATCH	LOW	11 SLABS	55.00	7.6

SAMPLE UNIT-190(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 79
-------------------------	--	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	13 SLABS	65.00	14.0
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	12 SLABS	60.00	8.0

SAMPLE UNIT-202(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 75
-------------------------	--	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	4 SLABS	20.00	10.0
70 SCALING/CRAZING	LOW	10 SLABS	50.00	12.2
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	8 SLABS	40.00	5.7

SAMPLE UNIT-21 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 59
-------------------------	--	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00	4.5
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	MEDIUM	3 SLABS	15.00	24.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	12 SLABS	60.00	9.0
66 SMALL PATCH	LOW	2 SLABS	10.00	1.1

SAMPLE UNIT-231(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 76
-------------------------	--	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	5.00	11.0
70 SCALING/CRAZING	LOW	8 SLABS	40.00	11.0
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	6 SLABS	30.00	4.0

SAMPLE UNIT-233(RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 78
-------------------------	--	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	17 SLABS	85.00	15.7
66 SMALL PATCH	LOW	6 SLABS	30.00	4.0

SAMPLE UNIT-44 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 71
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	MEDIUM	2 SLABS	10.00	16.8
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-46 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 76
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
64 DURABILITY CR	LOW	1 SLABS	5.00	1.8
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	2 SLABS	10.00	6.0
70 SCALING/CRAZING	LOW	8 SLABS	40.00	11.0
66 SMALL PATCH	LOW	4 SLABS	20.00	2.2

SAMPLE UNIT-49 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 69
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	2 SLABS	10.00	3.7
75 CORNER SPALLING	MEDIUM	1 SLABS	5.00	3.3
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	5.00	11.0
70 SCALING/CRAZING	LOW	4 SLABS	20.00	7.0
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-63 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 71
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00	4.5
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	3 SLABS	15.00	8.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	4 SLABS	20.00	2.2

SAMPLE UNIT-69 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 85	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
67 LG PATCH/UTIL	LOW	2 SLABS	10.00	6.0	
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	LOW	8 SLABS	40.00	5.7	

SAMPLE UNIT-70 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 77	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1	
63 LINEAR CR	LOW	2 SLABS	10.00	8.5	
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6	
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1	
66 SMALL PATCH	LOW	3 SLABS	15.00	1.6	

SAMPLE UNIT-75 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 81	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1	
63 LINEAR CR	LOW	1 SLABS	5.00	4.9	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	LOW	8 SLABS	40.00	5.7	

SAMPLE UNIT-85 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 84	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2	
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1	
66 SMALL PATCH	LOW	6 SLABS	30.00	4.0	

SAMPLE UNIT-91 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 65	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6	
70 SCALING/CRAZING	LOW	3 SLABS	15.00	5.6	
72 SHATTERED SLAB	MEDIUM	1 SLABS	5.00	19.3	
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5	
66 SMALL PATCH	LOW	7 SLABS	35.00	5.0	
66 SMALL PATCH	MEDIUM	1 SLABS	5.00	2.7	

SAMPLE UNIT-99 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 81
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	6 SLABS	30.00	9.4
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	11 SLABS	55.00	7.6
66 SMALL PATCH	MEDIUM	1 SLABS	5.00	2.7

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	31 SLABS	0.67	0.2
75 CORNER SPALLING	MEDIUM	10 SLABS	0.21	0.1
64 DURABILITY CR	LOW	10 SLABS	0.21	0.1
74 JOINT SPALLING	LOW	187 SLABS	4.09	2.0
74 JOINT SPALLING	MEDIUM	31 SLABS	0.67	0.7
65 JT SEAL DAMAGE	HIGH	830 SLABS	18.18	12.0
65 JT SEAL DAMAGE	LOW	3733 SLABS	81.79	2.0
67 LG PATCH/UTIL	LOW	197 SLABS	4.31	2.7
67 LG PATCH/UTIL	MEDIUM	41 SLABS	0.89	2.2
63 LINEAR CR	LOW	52 SLABS	1.13	1.1
63 LINEAR CR	MEDIUM	52 SLABS	1.13	2.8
70 SCALING/CRAZING	LOW	1348 SLABS	29.53	9.2
72 SHATTERED SLAB	MEDIUM	10 SLABS	0.21	0.1
73 SHRINKAGE CR	N/A	570 SLABS	12.48	1.8
66 SMALL PATCH	LOW	1473 SLABS	32.27	4.4
66 SMALL PATCH	MEDIUM	21 SLABS	0.46	0.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

JAD	RELATED DISTRESSES -	9.62 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	33.89 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	56.49 PERCENT DEDUCT VALUES.

BRANCH NAME -	OPERATIONAL APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A6B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	924

INSPECTION DATE -	09/06/89	PCI-	69	RATING-	GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	35
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	22
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	10.0

SAMPLE UNIT-19 (RANDOM)	SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 59
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
64 DURABILITY CR	LOW	1 SLABS	4.16	1.5
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0
67 LG PATCH/UTIL	LOW	1 SLABS	4.16	2.6
63 LINEAR CR	LOW	3 SLABS	12.50	10.0
63 LINEAR CR	MEDIUM	2 SLABS	8.33	16.9
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
66 SMALL PATCH	LOW	6 SLABS	25.00	3.2

SAMPLE UNIT-24 (RANDOM)

SAMPLE SIZE-

24 SLABS

SAMPLE PCI- 68

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0
67 LG PATCH/UTIL	LOW	4 SLABS	16.66	8.7
63 LINEAR CR	MEDIUM	1 SLABS	4.16	10.2
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	2 SLABS	8.33	1.3
66 SMALL PATCH	LOW	4 SLABS	16.66	1.8

SAMPLE UNIT-6 (RANDOM)

SAMPLE SIZE-

20 SLABS

SAMPLE PCI- 79

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
64 DURABILITY CR	LOW	14 SLABS	1.51	0.7
65 JT SEAL DAMAGE	MEDIUM	924 SLABS	100.00	7.0
67 LG PATCH/UTIL	LOW	68 SLABS	7.35	4.6
63 LINEAR CR	LOW	41 SLABS	4.43	4.3
63 LINEAR CR	MEDIUM	41 SLABS	4.43	10.6
70 SCALING/CRAZING	LOW	924 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	41 SLABS	4.43	1.0
66 SMALL PATCH	LOW	149 SLABS	16.12	1.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES =	31.70 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES =	16.38 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES =	51.91 PERCENT DEDUCT VALUES.

BRANCH NAME - OPERATIONAL APRON
BRANCH NUMBER - A7B

SLAB LENGTH - 25.0 LF
SLAB WIDTH - 25.0 LF

SECTION NUMBER - 1

NUMBER OF SLABS - 1148

INSPECTION DATE - 09/06/89 PCI- 67 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 56
 NUMBER OF SAMPLES SURVEYED- 5
 RECOMMENDED SAMPLES TO BE SURVEYED- 24
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 12.7

SAMPLE UNIT-10 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 72

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	LOW	2 SLABS	10.00	8.5
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	6 SLABS	30.00	4.2
66 SMALL PATCH	LOW	2 SLABS	10.00	1.1

SAMPLE UNIT-21 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 44

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	5 SLABS	25.00	15.5
63 LINEAR CR	MEDIUM	3 SLABS	15.00	24.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	1 SLABS	5.00	10.9
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1

SAMPLE UNIT-34 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 70

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1

SAMPLE UNIT-47 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 74

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-7 (RANDOM)

SAMPLE SIZE-

20 SLABS

SAMPLE PCI- 73

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	5 SLABS	25.00	3.5
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	11 SLABS	0.95	0.6
65 JT SEAL DAMAGE	HIGH	459 SLABS	39.98	12.0
65 JT SEAL DAMAGE	MEDIUM	689 SLABS	60.01	7.0
63 LINEAR CR	LOW	92 SLABS	8.01	7.1
63 LINEAR CR	MEDIUM	46 SLABS	4.00	10.0
70 SCALING/CRAZING	LOW	1148 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	11 SLABS	0.95	2.3
73 SHRINKAGE CR	N/A	230 SLABS	20.03	2.9
66 SMALL PATCH	LOW	46 SLABS	4.00	0.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	32.66 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	31.99 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	35.35 PERCENT DEDUCT VALUES.

BRANCH NAME - OPERATIONAL APRON
 BRANCH NUMBER - A8B
 SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
 SLAB WIDTH - 25.0 LF
 NUMBER OF SLABS - 81

INSPECTION DATE - 09/06/89 PCI- 47 RATING- FAIR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 4
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-2 (RANDOM)

SAMPLE SIZE-

20 SLABS

SAMPLE PCI- 47

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	HIGH	1 SLABS	5.00	16.2
63 LINEAR CR	LOW	2 SLABS	10.00	8.5
63 LINEAR CR	MEDIUM	2 SLABS	10.00	19.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	7 SLABS	35.00	5.0

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	81 SLABS	100.00	12.0
63 LINEAR CR	HIGH	4 SLABS	4.93	16.0
63 LINEAR CR	LOW	8 SLABS	9.87	8.4
63 LINEAR CR	MEDIUM	8 SLABS	9.87	18.8
70 SCALING/CRAZING	LOW	81 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	28 SLABS	34.56	4.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	56.03 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	15.56 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	28.40 PERCENT DEDUCT VALUES.

 BRANCH NAME - WARMUP APRON SECTION LENGTH - 480 LF
 BRANCH NUMBER - A9B SECTION WIDTH - 280 LF
 SECTION NUMBER - 1 SECTION AREA - 14933 SY

INSPECTION DATE - 09/06/89 PCI- 21 RATING- VERY POOR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 16
 NUMBER OF SAMPLES SURVEYED- 2
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 21

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	HIGH	5000 SF	100.00	78.9

 SAMPLE UNIT-6 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 21

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	HIGH	5000 SF	100.00	78.9

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
43 BLOCK CR	HIGH	134400 SF	100.00	78.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.

OTHER

RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - WARMUP
 BRANCH NUMBER - A10B
 SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
 SLAB WIDTH - 25.0 LF
 NUMBER OF SLABS - 224

INSPECTION DATE - 09/02/89 PCI- 55 RATING- FAIR
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 13
 NUMBER OF SAMPLES SURVEYED- 3
 RECOMMENDED SAMPLES TO BE SURVEYED- 10
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 10.0

SAMPLE UNIT-3 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 51	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0	
63 LINEAR CR	LOW	8 SLABS	33.33	17.6	
63 LINEAR CR	MEDIUM	3 SLABS	12.50	21.5	
70 SCALING/CRAZING	LOW	10 SLABS	41.66	11.2	
72 SHATTERED SLAB	LOW	1 SLABS	4.16	9.5	
73 SHRINKAGE CR	N/A	11 SLABS	45.83	6.6	

SAMPLE UNIT-6 (RANDOM)		SAMPLE SIZE-	36 SLABS	SAMPLE PCI- 66	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
75 CORNER SPALLING	LOW	2 SLABS	5.55	2.1	
65 JT SEAL DAMAGE	HIGH	36 SLABS	100.00	12.0	
63 LINEAR CR	MEDIUM	4 SLABS	11.11	20.1	
70 SCALING/CRAZING	LOW	3 SLABS	8.33	3.2	
73 SHRINKAGE CR	N/A	8 SLABS	22.22	3.1	
66 SMALL PATCH	LOW	3 SLABS	8.33	1.0	

SAMPLE UNIT-9 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 47	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	24 SLABS	100.00	12.0	
63 LINEAR CR	LOW	7 SLABS	29.16	16.7	
70 SCALING/CRAZING	LOW	8 SLABS	33.33	9.8	
72 SHATTERED SLAB	LOW	1 SLABS	4.16	9.5	
72 SHATTERED SLAB	MEDIUM	2 SLABS	8.33	25.2	
73 SHRINKAGE CR	N/A	7 SLABS	29.16	4.0	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

75 CORNER SPALLING	LOW	5 SLABS	2.23	0.7
65 JT SEAL DAMAGE	HIGH	160 SLABS	71.42	12.0
65 JT SEAL DAMAGE	MEDIUM	64 SLABS	28.57	7.0
63 LINEAR CR	LOW	40 SLABS	17.85	12.6
63 LINEAR CR	MEDIUM	19 SLABS	8.48	17.1
70 SCALING/CRAZING	LOW	56 SLABS	25.00	8.2
72 SHATTERED SLAB	LOW	5 SLABS	2.23	5.4
72 SHATTERED SLAB	MEDIUM	5 SLABS	2.23	2.8
73 SHRINKAGE CR	N/A	69 SLABS	30.80	4.3
66 SMALL PATCH	LOW	8 SLABS	3.57	0.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	53.76 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	26.95 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	19.29 PERCENT DEDUCT VALUES.

BRANCH NAME -	CHRISTMAS TREE APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A11C	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	540

INSPECTION DATE -	09/05/89	PCI=	76	RATING=	VERY GOOD
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	16
NUMBER OF SAMPLES SURVEYED-	4
RECOMMENDED SAMPLES TO BE SURVEYED-	17
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	8.1

SAMPLE UNIT-11 (RANDOM)		SAMPLE SIZE-	30 SLABS	SAMPLE PCI-	64
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	30 SLABS	100.00	7.0	
67 LG PATCH/UTIL	MEDIUM	2 SLABS	6.66	13.3	
63 LINEAR CR	LOW	1 SLABS	3.33	3.3	
63 LINEAR CR	MEDIUM	1 SLABS	3.33	8.3	
70 SCALING/CRAZING	LOW	30 SLABS	100.00	17.0	

SAMPLE UNIT-9 (RANDOM)		SAMPLE SIZE-	30 SLABS	SAMPLE PCI-	79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	3.33	1.7	
65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	15 SLABS	50.00	12.2	

SAMPLE UNIT-16 (RANDOM)		SAMPLE SIZE-	18 SLABS	SAMPLE PCI-	82
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	

74 JOINT SPALLING	LOW	1 SLABS	5.55	2.3
67 LG PATCH/UTIL	LOW	5 SLABS	27.77	12.7
73 SHRINKAGE CR	N/A	4 SLABS	22.22	3.1

SAMPLE UNIT-5 (RANDOM)	SAMPLE SIZE-	30 SLABS	SAMPLE PCI- 79
------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	4 SLABS	13.33	4.9
65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0
70 SCALING/CRAZING	LOW	8 SLABS	26.66	8.5
66 SMALL PATCH	LOW	1 SLABS	3.33	0.4

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	20 SLABS	3.70	1.3
74 JOINT SPALLING	LOW	10 SLABS	1.85	1.2
74 JOINT SPALLING	MEDIUM	5 SLABS	0.92	0.9
65 JT SEAL DAMAGE	HIGH	300 SLABS	55.55	12.0
65 JT SEAL DAMAGE	MEDIUM	150 SLABS	27.77	7.0
67 LG PATCH/UTIL	LOW	25 SLABS	4.62	2.9
67 LG PATCH/UTIL	MEDIUM	10 SLABS	1.85	4.6
63 LINEAR CR	LOW	5 SLABS	0.92	0.9
63 LINEAR CR	MEDIUM	5 SLABS	0.92	2.3
70 SCALING/CRAZING	LOW	265 SLABS	49.07	12.1
73 SHRINKAGE CR	N/A	20 SLABS	3.70	0.9
66 SMALL PATCH	LOW	5 SLABS	0.92	0.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	6.93 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	41.13 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	51.95 PERCENT DEDUCT VALUES.

BRANCH NAME -	CHRISTMAS TREE APRON	SLAB LENGTH -	12.5 LF
BRANCH NUMBER -	A12C	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	1000

INSPECTION DATE -	09/05/89	PCI-	55	RATING-	FAIR
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	70
NUMBER OF SAMPLES SURVEYED-	6
RECOMMENDED SAMPLES TO BE SURVEYED-	49
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	24.1

SAMPLE UNIT-10 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 20
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	3 SLABS	15.00	11.4
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6
72 SHATTERED SLAB	LOW	7 SLABS	35.00	35.0
72 SHATTERED SLAB	MEDIUM	7 SLABS	35.00	50.9

SAMPLE UNIT-24 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 33
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
63 LINEAR CR	MEDIUM	2 SLABS	10.00	19.0
72 SHATTERED SLAB	LOW	3 SLABS	15.00	22.3
72 SHATTERED SLAB	MEDIUM	3 SLABS	15.00	33.3
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6
66 SMALL PATCH	MEDIUM	3 SLABS	15.00	7.6

SAMPLE UNIT-51 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 54
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
74 JOINT SPALLING	LOW	2 SLABS	10.00	3.5
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
72 SHATTERED SLAB	LOW	1 SLABS	5.00	10.9
72 SHATTERED SLAB	MEDIUM	2 SLABS	10.00	27.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

SAMPLE UNIT-66 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 67
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	4 SLABS	20.00	15.0
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
74 JOINT SPALLING	LOW	6 SLABS	30.00	7.8
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	5 SLABS	25.00	3.5

SAMPLE UNIT-69 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 79
-------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	7 SLABS	35.00	10.7
74 JOINT SPALLING	LOW	4 SLABS	20.00	5.9
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0

SAMPLE UNIT-70 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PC - 77	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE

75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
73 SHRINKAGE CR	N/A	6 SLABS	30.00	4.2

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
---------------	----------	----------	-------------	--------------

62 CORNER BR	LOW	58 SLABS	5.80	4.8
75 CORNER SPALLING	LOW	83 SLABS	8.30	3.1
74 JOINT SPALLING	LOW	108 SLABS	10.80	3.7
65 JT SEAL DAMAGE	HIGH	1000 SLABS	100.00	12.0
63 LINEAR CR	LOW	42 SLABS	4.20	4.1
63 LINEAR CR	MEDIUM	25 SLABS	2.50	6.2
72 SHATTERED SLAB	LOW	92 SLABS	9.20	16.7
72 SHATTERED SLAB	MEDIUM	100 SLABS	10.00	27.0
73 SHRINKAGE CR	N/A	100 SLABS	10.00	1.5
66 SMALL PATCH	LOW	17 SLABS	1.70	0.2
65 SMALL PATCH	MEDIUM	25 SLABS	2.50	1.3

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	72.95 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	14.89 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	12.16 PERCENT DEDUCT VALUES.

REPORT DATE- 11/02/89 PAVEMENT INSPECTION

BRANCH NAME -	ALERT APRON	SLAB LENGTH -	20.0 LF
BRANCH NUMBER -	A13B	SLAB WIDTH -	20.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	15

INSPECTION DATE -	09/05/89	PCI-	44	RATING-	FAIR
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	1
NUMBER OF SAMPLES SURVEYED-	1

RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	15 SLABS	SAMPLE PCI- 44	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE

75 CORNER SPALLING	LOW	2 SLABS	13.33	4.9
74 JOINT SPALLING	LOW	1 SLAB	6.66	2.6
65 JT SEAL DAMAGE	LOW	15 SLABS	100.00	2.0
63 LINEAR CR	LOW	1 SLABS	6.66	6.2

63 LINEAR CR	MEDIUM	8 SLABS	53.33	46.3
70 SCALING/CRAZING	LOW	5 SLABS	33.33	9.8
73 SHRINKAGE CR	N/A	3 SLABS	20.00	2.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	2 SLABS	13.33	4.9
74 JOINT SPALLING	LOW	1 SLABS	6.66	2.6
65 JT SEAL DAMAGE	LOW	15 SLABS	100.00	2.0
63 LINEAR CR	LOW	1 SLABS	6.66	6.2
63 LINEAR CR	MEDIUM	8 SLABS	53.33	46.3
70 SCALING/CRAZING	LOW	5 SLABS	33.33	9.8
73 SHRINKAGE CR	N/A	3 SLABS	20.00	2.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	70.28 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	2.68 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	27.04 PERCENT DEDUCT VALUES.

BRANCH NAME -	ALERT APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A14B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	210

INSPECTION DATE -	09/05/89	PCI-	99	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	9
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	1.4

SAMPLE UNIT-4 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-100
------------------------	--------------	----------	----------------

NO DISTRESS

SAMPLE UNIT-7 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 98
------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	105 SLABS	50.00	2.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

 BRANCH NAME - MAINTENANCE APRON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A15B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 36

INSPECTION DATE - 09/05/89 PCI- 68 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 2
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 18 SLABS SAMPLE PCI- 68

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	18 SLABS	100.00	2.0
63 LINEAR CR	LOW	15 SLABS	83.33	22.0
70 SCALING/CRAZING	LOW	12 SLABS	66.66	14.1
66 SMALL PATCH	LOW	2 SLABS	11.11	1.1

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	36 SLABS	100.00	2.0
63 LINEAR CR	LOW	30 SLABS	83.33	22.0
70 SCALING/CRAZING	LOW	24 SLABS	66.66	14.1
66 SMALL PATCH	LOW	4 SLABS	11.11	1.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 56.12 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 5.10 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 38.78 PERCENT DEDUCT VALUES.

 BRANCH NAME - MAINTENANCE APRON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A16B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMEER OF SLABS - 60

INSPECTION DATE - 09/07/89 PCI- 60 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	19.7

SAMPLE UNIT-1 (RANDOM)		SAMPLE SIZE-	30 SLABS	SAMPLE PCI- 74
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	6 SLABS	25.00	6.9
74 JOINT SPALLING	MEDIUM	9 SLABS	37.50	21.6
65 JT SEAL DAMAGE	MEDIUM	30 SLABS	100.00	7.0

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	30 SLABS	SAMPLE PCI- 46
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	32 SLABS	100.00	7.0
63 LINEAR CR	LOW	3 SLABS	9.37	8.0
63 LINEAR CR	MEDIUM	9 SLABS	28.12	33.7
70 SCALING/CRAZING	LOW	32 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	10 SLABS	31.25	4.4
66 SMALL PATCH	LOW	13 SLABS	40.62	5.7
66 SMALL PATCH	MEDIUM	2 SLABS	6.25	3.3

EXTRAPOLATEL DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	2 SLABS	4.16	2.0
74 JOINT SPALLING	MEDIUM	4 SLABS	8.33	6.9
65 JT SEAL DAMAGE	MEDIUM	48 SLABS	100.00	7.0
63 LINEAR CR	LOW	4 SLABS	8.33	7.3
63 LINEAR CR	MEDIUM	11 SLABS	22.91	30.2
70 SCALING/CRAZING	LOW	38 SLABS	79.16	15.1
73 SHRINKAGE CR	N/A	12 SLABS	25.00	3.5
66 SMALL PATCH	LOW	16 SLABS	33.33	4.6
66 SMALL PATCH	MEDIUM	2 SLABS	4.16	2.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	47.59 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	8.88 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	43.53 PERCENT DEDUCT VALUES.

BRANCH NAME -	MAINTENANCE APRON	SECTION LENGTH -	365 LF
BRANCH NUMBER -	A17B	SECTION WIDTH -	600 LF
SECTION NUMBER -	1	SECTION AREA -	24333 SY

INSPECTION DATE - 09/05/89 PCI- 64 RATING- GOOD

CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 46
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED NO. OF SAMPLE UNITS TO BE SURVEYED. 20

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI 64
DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
43 BLOCK CR LOW 5000 SF 100.00 35.7

SAMPLE UNIT-33 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 64
DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
43 BLOCK CR LOW 5000 SF 100.00 35.7

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-
DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
43 BLOCK CR LOW 219000 SF 100.00 35.7

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

BRANCH NAME - COMPASS ROSE SLAB LENGTH - 25.0 LF
BRANCH NUMBER - A18C SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 28

INSPECTION DATE - 09/05/89 PCI- 49 RATING- FAIR
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 2
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 16 SLABS SAMPLE PCI- 49
DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
65 JT SEAL DAMAGE HIGH 16 SLABS 100.00 12.0
63 LINEAR CR LOW 7 SLABS 43.75 19.6
70 SCALING/CRAZING LOW 16 SLABS 100.00 17.0
72 SHATTERED SLAB LOW 2 SLABS 12.50 20.0

73 SHRINKAGE CR	N/A	2 SLABS	12.50	1.8
66 SMALL PATCH	LOW	1 SLABS	6.25	0.8

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	28 SLABS	100.00	12.0
63 LINEAR CR	LOW	12 SLABS	42.85	19.4
70 SCALING/CRAZING	LOW	28 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	4 SLABS	14.28	21.6
73 SHRINKAGE CR	N/A	4 SLABS	14.28	2.0
66 SMALL PATCH	LOW	2 SLABS	7.14	0.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	56.24 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	16.46 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	27.30 PERCENT DEDUCT VALUES.

 BRANCH NAME - WEST ARPON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A19B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 980

INSPECTION DATE - 09/05/89 PCI- 65 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 45
 NUMBER OF SAMPLES SURVEYED- 5
 RECOMMENDED SAMPLES TO BE SURVEYED- 24
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 12.0

SAMPLE UNIT-11 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 71

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0
63 LINEAR CR	LOW	3 SLABS	14.28	10.9
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	6 SLABS	28.57	3.9

SAMPLE UNIT-21 (RANDOM) SAMPLE SIZE- 21 SLABS SAMPLE PCI- 72

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	3 SLABS	14.28	4.5
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0
70 SCALING/CRAZING	MEDIUM	1 SLABS	4.76	6.6
73 SHRINKAGE CR	N/A	1 SLABS	4.76	1.0
66 SMALL PATCH	LOW	4 SLABS	19.04	2.1

SAMPLE UNIT-32 (RANDOM)		SAMPLE SIZE-	21 SLABS	SAMPLE PCI- 55	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	2 SLABS	9.52	3.3	
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0	
67 LG PATCH/UTIL	LOW	1 SLABS	4.76	2.9	
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0	
70 SCALING/CRAZING	MEDIUM	2 SLABS	9.52	12.0	
72 SHATTERED SLAB	LOW	2 SLABS	9.52	17.1	
73 SHRINKAGE CR	N/A	8 SLABS	38.09	5.5	
66 SMALL PATCH	LOW	2 SLABS	9.52	1.0	

SAMPLE UNIT-37 (RANDOM)		SAMPLE SIZE-	21 SLABS	SAMPLE PCI- 50	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	4.76	2.1	
74 JOINT SPALLING	MEDIUM	1 SLABS	4.76	4.3	
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0	
63 LINEAR CR	LOW	6 SLABS	28.57	16.5	
63 LINEAR CR	MEDIUM	2 SLABS	9.52	18.4	
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	10 SLABS	47.61	6.9	

SAMPLE UNIT-39 (RANDOM)		SAMPLE SIZE-	21 SLABS	SAMPLE PCI- 78	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	4.76	2.1	
65 JT SEAL DAMAGE	MEDIUM	21 SLABS	100.00	7.0	
70 SCALING/CRAZING	LOW	21 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	1 SLABS	4.76	1.0	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	65 SLABS	6.63	2.6	
74 JOINT SPALLING	MEDIUM	9 SLABS	0.91	0.9	
65 JT SEAL DAMAGE	MEDIUM	980 SLABS	100.00	7.0	
67 LG PATCH/UTIL	LOW	9 SLABS	0.91	0.6	
63 LINEAR CR	LOW	84 SLABS	8.57	7.4	
63 LINEAR CR	MEDIUM	19 SLABS	1.93	4.8	
70 SCALING/CRAZING	LOW	980 SLABS	100.00	17.0	
70 SCALING/CRAZING	MEDIUM	28 SLABS	2.85	4.1	
72 SHATTERED SLAB	LOW	19 SLABS	1.93	4.8	
73 SHRINKAGE CR	N/A	243 SLABS	24.79	3.4	
66 SMALL PATCH	LOW	56 SLABS	5.71	0.7	

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	31.89 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	13.13 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	54.97 PERCENT DEDUCT VALUES.

BRANCH NAME -	WEST APRON	SLAB LENGTH -	15.0 LF
BRANCH NUMBER -	A21B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	680

INSPECTION DATE -	09/04/89.	PCI-	36	RATING-	POOR
CCNDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-	

TOTAL NUMBER OF SAMPLES IN SECTION-	82
NUMBER OF SAMPLES SURVEYED-	6
RECOMMENDED SAMPLES TO BE SURVEYED-	40
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	18.7

SAMPLE UNIT-13 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	16
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	3 SLABS	15.00	11.3
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	3 SLABS	15.00	22.3
72 SHATTERED SLAB	MEDIUM	14 SLABS	70.00	71.3
66 SMALL PATCH	MEDIUM	1 SLABS	5.00	2.7

SAMPLE UNIT-23 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	25
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	7 SLABS	35.00	18.0
72 SHATTERED SLAB	LOW	3 SLABS	15.00	22.3
72 SHATTERED SLAB	MEDIUM	9 SLABS	45.00	57.2
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

SAMPLE UNIT-25 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	36
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	2 SLABS	10.00	3.7
75 CORNER SPALLING	MEDIUM	1 SLABS	5.00	3.3
74 JOINT SPALLING	MEDIUM	3 SLABS	15.00	10.9
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
63 LINEAR CR	LOW	10 SLABS	50.00	20.2
63 LINEAR CR	MEDIUM	2 SLABS	10.00	19.0
72 SHATTERED SLAB	LOW	7 SLABS	35.00	35.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

SAMPLE UNIT-3 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 51	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	4 SLABS	20.00	15.0	
75 CORNER SPALLING	HIGH	1 SLABS	5.00	5.1	
75 CORNER SPALLING	LOW	2 SLABS	10.00	3.7	
64 DURABILITY CR	LOW	2 SLABS	10.00	3.3	
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
63 LINEAR CR	LOW	4 SLABS	20.00	13.7	
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	LOW	5 SLABS	25.00	3.2	

SAMPLE UNIT-38 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 65	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	3 SLABS	15.00	11.4	
74 JOINT SPALLING	LOW	3 SLABS	15.00	4.7	
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0	
63 LINEAR CR	LOW	5 SLABS	25.00	15.5	
72 SHATTERED SLAB	LOW	1 SLABS	5.00	10.9	
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1	
66 SMALL PATCH	LOW	2 SLABS	10.00	1.1	

SAMPLE UNIT-50 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 23	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	MEDIUM	1 SLABS	5.00	8.2	
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00	4.5	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1	
67 LG PATCH/UTIL	MEDIUM	1 SLABS	5.00	11.0	
63 LINEAR CR	LOW	3 SLABS	15.00	11.3	
63 LINEAR CR	MEDIUM	3 SLABS	15.00	24.0	
72 SHATTERED SLAB	MEDIUM	7 SLABS	35.00	50.9	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
62 CORNER BR	LOW	40 SLABS	5.88	4.8	
62 CORNER BR	MEDIUM	6 SLABS	0.88	1.5	
75 CORNER SPALLING	HIGH	6 SLABS	0.88	1.0	
75 CORNER SPALLING	LOW	23 SLABS	3.38	1.2	
75 CORNER SPALLING	MEDIUM	6 SLABS	0.88	0.7	
64 DURABILITY CR	LOW	11 SLABS	1.61	0.8	
74 JOINT SPALLING	LOW	23 SLABS	3.38	1.7	
74 JOINT SPALLING	MEDIUM	23 SLABS	3.38	3.2	
65 JT SEAL DAMAGE	HIGH	340 SLABS	50.00	12.0	

65 JT SEAL DAMAGE	LOW	227 SLABS	33.38	2.0
67 LG PATCH/UTIL	LOW	6 SLABS	0.88	0.6
67 LG PATCH/UTIL	MEDIUM	6 SLABS	0.88	2.2
63 LINEAR CR	LOW	181 SLABS	26.61	15.9
63 LINEAR CR	MEDIUM	34 SLABS	5.00	11.6
70 SCALING/CRAZING	LOW	113 SLABS	16.61	6.0
72 SHATTERED SLAB	LOW	79 SLABS	11.61	19.2
72 SHATTERED SLAB	MEDIUM	170 SLABS	25.00	43.0
73 SHRINKAGE CR	N/A	34 SLABS	5.00	1.0
66 SMALL PATCH	LOW	40 SLABS	5.88	0.7
66 SMALL PATCH	MEDIUM	6 SLABS	0.88	0.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	74.13 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	11.43 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	14.44 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	15.0 LF
BRANCH NUMBER -	A22B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	48

INSPECTION DATE -	09/01/89	PCI-	80	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	15
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	1.1

SAMPLE UNIT-13 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
63 LINEAR CR	LOW	2 SLABS	10.00	8.5	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	81
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	

70 SCALING/CRAZING LOW 20 SLABS 100.00 17.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	LOW	1 SLABS	2.08	1.3
65 JT SEAL DAMAGE	MEDIUM	32 SLABS	66.66	7.0
63 LINEAR CR	LOW	2 SLABS	4.16	4.1
70 SCALING/CRAZING	LOW	48 SLABS	100.00	17.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	13.95 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	23.81 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	62.24 PERCENT DEDUCT VALUES.

BRANCH NAME - HARD STAND SLAB LENGTH - 20.0 LF
BRANCH NUMBER - A23B SLAB WIDTH - 20.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 2

INSPECTION DATE - 09/04/89 PCI- 100 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 2 SLABS SAMPLE PCI-100

NO DISTRESS

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

NO DISTRESS

BRANCH NAME - NORTH APRON SLAB LENGTH - 12.5 LF
BRANCH NUMBER - A24B SLAB WIDTH - 12.5 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 228

INSPECTION DATE - 09/01/89 PCI- 81 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 11
NUMBER OF SAMPLES SURVEYED- 2
RECOMMENDED SAMPLES TO BE SURVEYED- 7
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 3.5

SAMPLE UNIT-2 (RANDOM) SAMPLE SIZE- 24 SLABS SAMPLE PCI- 78

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0
63 LINEAR CR	LOW	3 SLABS	12.50	10.0
70 SCALING/CRAZING	LOW	6 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	8 SLABS	33.33	4.7

SAMPLE UNIT-7 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 83

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	5 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	11 SLABS	55.00	8.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	228 SLABS	100.00	7.0
63 LINEAR CR	LOW	16 SLABS	7.01	6.4
70 SCALING/CRAZING	LOW	57 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	98 SLABS	42.98	6.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	23.02 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	25.18 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	51.80 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	12.5 LF
BRANCH NUMBER -	A25B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	900

INSPECTION DATE -	09/01/89	PCI-	86	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	44
NUMBER OF SAMPLES SURVEYED-	4
RECOMMENDED SAMPLES TO BE SURVEYED-	23
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	11.0

SAMPLE UNIT-22 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 96

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	1 SLABS	5.00	2.1

SAMPLE UNIT-3 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 77
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
63 LINEAR CR	MEDIUM	1 SLABS	5.00	11.6
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

SAMPLE UNIT-35 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 94
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	2 SLABS	10.00	4.0

SAMPLE UNIT-9 (RANDOM)		SAMPLE SIZE	20 SLABS	SAMPLE PCI- 75
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
63 LINEAR CR	LOW	4 SLABS	20.00	13.7
70 SCALING/CRAZING	LOW	13 SLABS	65.00	14.0
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	900 SLABS	100.00	2.0
63 LINEAR CR	LOW	56 SLABS	6.22	5.9
63 LINEAR CR	MEDIUM	11 SLABS	1.22	3.0
70 SCALING/CRAZING	LOW	203 SLABS	22.55	7.6
73 SHRINKAGE CR	N/A	23 SLABS	2.55	0.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	46.11 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	10.36 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	43.52 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A26B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	276

INSPECTION DATE -	09/01/89	PCI-	67	RATING-	GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	11
NUMBER OF SAMPLES SURVEYED-	2

RECOMMENDED SAMPLES TO BE SURVEYED-
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-

8
2.1

SAMPLE UNIT-4 (RANDOM) SAMPLE SIZE- 24 SLABS SAMPLE PCI- 68

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	24 SLABS	100.00	7.0
67 LG PATCH/UTIL	MEDIUM	1 SLABS	4.16	9.7
63 LINEAR CR	LOW	6 SLABS	25.00	15.5
70 SCALING/CRAZING	LOW	6 SLABS	25.00	8.2
73 SHRINKAGE CR	N/A	9 SLABS	37.50	5.4
66 SMALL PATCH	LOW	3 SLABS	12.50	1.2
66 SMALL PATCH	LOW	2 SLABS	8.33	1.0

SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 65

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	6 SLABS	30.00	9.4
70 SCALING/CRAZING	MEDIUM	2 SLABS	10.00	12.5
72 SHATTERED SLAB	LOW	1 SLABS	5.00	10.9
73 SHRINKAGE CR	N/A	14 SLABS	70.00	10.7
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	276 SLABS	100.00	7.0
67 LG PATCH/UTIL	MEDIUM	6 SLABS	2.17	5.3
63 LINEAR CR	LOW	38 SLABS	13.76	10.6
70 SCALING/CRAZING	LOW	75 SLABS	27.17	8.7
70 SCALING/CRAZING	MEDIUM	13 SLABS	4.71	6.5
72 SHATTERED SLAB	LOW	6 SLABS	2.17	5.3
73 SHRINKAGE CR	N/A	144 SLABS	52.17	7.6
66 SMALL PATCH	LOW	38 SLABS	13.76	1.4

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	30.34 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	13.36 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	56.30 PERCENT DEDUCT VALUES.

BRANCH NAME - NORTH APRON SLAB LENGTH - 25.0 LF
BRANCH NUMBER - A28B SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1 NUMBER OF SLABS - 264

INSPECTION DATE - 09/04/89 PCI- 60 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	11
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	11
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	19.0

SAMPLE UNIT-11 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI-	73
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	24 SLABS	100.00	12.0	
67 LG PATCH/UTIL	LOW	1 SLABS	4.16	2.6	
63 LINEAR CR	LOW	1 SLABS	4.16	4.1	
63 LINEAR CR	MEDIUM	1 SLABS	4.16	10.2	
70 SCALING/CRAZING	LOW	2 SLABS	8.33	3.2	
73 SHRINKAGE CR	N/A	2 SLABS	8.33	1.3	

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	24 SLABS	SAMPLE PCI-	46
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	24 SLABS	100.00	12.0	
67 LG PATCH/UTIL	LOW	1 SLABS	4.16	2.6	
63 LINEAR CR	LOW	2 SLABS	8.33	7.3	
63 LINEAR CR	MEDIUM	2 SLABS	8.33	16.9	
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0	
72 SHATTERED SLAB	LOW	3 SLABS	12.50	20.0	
73 SHRINKAGE CR	N/A	6 SLABS	25.00	3.5	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	264 SLABS	100.00	12.0	
67 LG PATCH/UTIL	LOW	11 SLABS	4.16	2.6	
63 LINEAR CR	LOW	17 SLABS	6.43	6.0	
63 LINEAR CR	MEDIUM	17 SLABS	6.43	13.9	
70 SCALING/CRAZING	LOW	143 SLABS	54.16	12.7	
72 SHATTERED SLAB	LOW	17 SLABS	6.43	13.0	
73 SHRINKAGE CR	N/A	44 SLABS	16.66	2.3	

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	52.64 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	19.20 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	28.16 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A29B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	176

INSPECTION DATE - 09/04/89 PCI= 67 RATING= GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION= 9
 NUMBER OF SAMPLES SURVEYED= 2
 RECOMMENDED SAMPLES TO BE SURVEYED= 5
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED= 0.7

 SAMPLE UNIT-3 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 66

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	1 SLABS	5.00	4.0
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0

 SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 67

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	1 SLABS	5.00	3.1
63 LINEAR CR	LOW	1 SLABS	5.00	4.9
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	4 SLABS	20.00	2.9

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
62 CORNER BR	LOW	4 SLABS	2.27	1.7
65 JT SEAL DAMAGE	HIGH	176 SLABS	100.00	12.0
67 LG PATCH/UTIL	LOW	9 SLABS	5.11	3.2
63 LINEAR CR	LOW	9 SLABS	5.11	4.9
70 SCALING/CRAZING	LOW	176 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	18 SLABS	10.22	1.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES =	16.38 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES =	29.78 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES =	53.85 PERCENT DEDUCT VALUES.

 BRANCH NAME - NORTH APRON SLAB LENGTH - 15.0 LF
 BRANCH NUMBER - A30B SLAB WIDTH - 12.5 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 700

INSPECTION DATE - 09/04/89 PCI= 71 RATING= VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION--	54
NUMBER OF SAMPLES SURVEYED--	5
RECOMMENDED SAMPLES TO BE SURVEYED--	11
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED--	6.3

SAMPLE UNIT-15 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 73	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6	

SAMPLE UNIT-19 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 60	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
63 LINEAR CR	LOW	2 SLABS	10.00	8.5	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
72 SHATTERED SLAB	LOW	2 SLABS	10.00	17.8	
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5	

SAMPLE UNIT-33 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 72	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
75 CORNER SPALLING	MEDIUM	1 SLABS	5.00	3.3	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5	

SAMPLE UNIT-48 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 76	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
74 JOINT SPALLING	LOW	1 SLABS	5.00	2.2	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	7 SLABS	1.00	0.3
75 CORNER SPALLING	MEDIUM	7 SLABS	1.00	0.8
74 JOINT SPALLING	LOW	7 SLABS	1.00	0.6
65 JT SEAL DAMAGE	HIGH	700 SLABS	100.00	12.0
63 LINEAR CR	LOW	14 SLABS	2.00	2.0
70 SCALING/CRAZING	LOW	700 SLABS	100.00	17.0
72 SHATTERED SLAB	LOW	14 SLABS	2.00	5.0
73 SHRINKAGE CR	N/A	42 SLABS	6.00	1.1
66 SMALL PATCH	LOW	7 SLABS	1.00	0.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	17.99 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	30.85 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	51.16 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	15.0 LF
BRANCH NUMBER -	A33B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	480

INSPECTION DATE -	09/01/89	PCI-	77	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	24
NUMBER OF SAMPLES SURVEYED-	6
RECOMMENDED SAMPLES TO BE SURVEYED-	5
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	4.2

SAMPLE UNIT-14 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	79
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	MEDIUM	1 SLABS	5.00	4.5
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0
70 SCALING/CRAZING	LOW	11 SLABS	55.00	12.9
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1

SAMPLE UNIT-18 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	71
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	5.00	1.9
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6
66 SMALL PATCH	MEDIUM	1 SLABS	5.00	2.7

SAMPLE UNIT-22 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	LOW	8 SLABS	40.00	5.7	

SAMPLE UNIT-24 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 80	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
63 LINEAR CR	LOW	2 SLABS	10.00	8.5	
70 SCALING/CRAZING	LOW	6 SLABS	30.00	9.4	
73 SHRINKAGE CR	N/A	3 SLABS	15.00	2.1	

SAMPLE UNIT-4 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 74	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0	
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	
66 SMALL PATCH	MEDIUM	2 SLABS	10.00	5.5	

SAMPLE UNIT-5 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 82	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
70 SCALING/CRAZING	LOW	16 SLABS	80.00	15.2	
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6	

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
75 CORNER SPALLING	LOW	4 SLABS	0.83	0.2	
74 JOINT SPALLING	MEDIUM	4 SLABS	0.83	0.8	
65 JT SEAL DAMAGE	HIGH	240 SLABS	50.00	12.0	
65 JT SEAL DAMAGE	MEDIUM	240 SLABS	50.00	7.0	
63 LINEAR CR	LOW	8 SLABS	1.66	1.6	
70 SCALING/CRAZING	LOW	372 SLABS	77.50	15.1	
73 SHRINKAGE CR	N/A	40 SLABS	8.33	1.3	
66 SMALL PATCH	LOW	40 SLABS	8.33	1.0	
66 SMALL PATCH	MEDIUM	12 SLABS	2.50	1.3	

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	3.97 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	47.15 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	48.88 PERCENT DEDUCT VALUES.

BRANCH NAME - OPERATIONAL APRON	SLAB LENGTH - 25 LF
BRANCH NUMBER - A35B	SLAB WIDTH - 25 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 444

INSPECTION DATE 09/04/89	PCI-	RATING-	
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	24
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	15

SAMPLE UNIT-2 (RANDOM)	SAMPLE SIZE-	20 SLABS	SAMPLE PCI- 71
------------------------	--------------	----------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100	7
70 SCLNG/MAP CRAK	LOW	20 SLABS	100	17
73 SHRINK CRACK	LOW	4 SLABS	20	3
63 LONG/TRANS CRACK	MEDIUM	1 SLAB	5	12

BRANCH NAME - BLDG APRON	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - A38B	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 30

INSPECTION DATE - 09/01/89	PCI- 43	RATING- FAIR	
CONDITION- RIDING-	SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	6 SLABS	SAMPLE PCI- 43
------------------------	--------------	---------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	MEDIUM	1 SLABS	16.66	10.4
65 JT SEAL DAMAGE	HIGH	6 SLABS	100.00	12.0
63 LINEAR CR	LOW	2 SLABS	33.33	17.6
63 LINEAR CR	MEDIUM	2 SLABS	33.33	36.9
73 SHRINKAGE CR	N/A	2 SLABS	33.33	4.7

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	MEDIUM	5 SLABS	16.66	10.4
65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0
63 LINEAR CR	LOW	10 SLABS	33.33	17.6

63 LINEAR CR	MEDIUM	10 SLABS	33.33	36.9
73 SHRINKAGE CR	N/A	10 SLABS	33.33	4.7

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	66.79 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	14.71 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	18.50 PERCENT DEDUCT VALUES.

BRANCH NAME -	BLDG APRON	SLAB LENGTH -	20.0 LF
BRANCH NUMBER -	A39B	SLAB WIDTH -	20.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	28

INSPECTION DATE -	09/03/89	PCI-	85	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	28 SLABS	SAMPLE PCI-	85
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
72 SHATTERED SLAB	LOW	2 SLABS	7.14	14.0
73 SHRINKAGE CR	N/A	1 SLABS	3.57	0.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
72 SHATTERED SLAB	LOW	2 SLABS	7.14	14.0
73 SHRINKAGE CR	N/A	1 SLABS	3.57	0.9

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	93.96 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	6.04 PERCENT DEDUCT VALUES.

BRANCH NAME -	DANGEROUS CARGO PAD	SECTION LENGTH -	1840 LF
BRANCH NUMBER -	A40B	SECTION WIDTH -	250 LF
SECTION NUMBER -	1	SECTION AREA -	51111 SY

INSPECTION DATE -	09/04/89	PCI-	89	RATING-	EXCELLENT
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	90
-------------------------------------	----

NUMBER OF SAMPLES SURVEYED-	9
RECOMMENDED SAMPLES TO BE SURVEYED-	6
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	5.0

SAMPLE UNIT-16 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 87	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	230 LF	4.60	13.1

SAMPLE UNIT-22 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 95	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	45 LF	0.90	5.1

SAMPLE UNIT-26 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 88	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	195 LF	3.90	11.7

SAMPLE UNIT-30 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 84	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	300 LF	6.00	16.0

SAMPLE UNIT-51 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 85	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	275 LF	5.50	15.0

SAMPLE UNIT-56 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 99	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	2 LF	0.04	1.0

SAMPLE UNIT-60 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 85	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
45 DEPRESSION	LOW	4 SF	0.08	0.2
48 LONG/TRANS CR	LOW	260 LF	5.20	14.4

SAMPLE UNIT-65 (RANDOM)		SAMPLE SIZE- 5000 SF	SAMPLE PCI- 87	
-------------------------	--	----------------------	----------------	--

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	220 LF	4.40	12.7

SAMPLE UNIT-88 (RANDOM)	SAMPLE SIZE- 5000 SF	SAMPLE PCI- 87
-------------------------	----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
48 LONG/TRANS CR	LOW	225 LF	4.50	12.9
48 LONG/TRANS CR	MEDIUM	50 LF	1.00	11.5

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
45 DEPRESSION	LOW	41 SF	0.00	0.0
48 LONG/TRANS CR	LOW	17905 LF	3.89	11.6
48 LONG/TRANS CR	MEDIUM	511 LF	0.11	4.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - APRON	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - A45B	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 70

INSPECTION DATE - 09/02/89	PCI- 88	RATING- EXCELLENT
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	4
NUMBER OF SAMPLES SURVEYED-	1

RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-3 (RANDOM)	SAMPLE SIZE- 20 SLABS	SAMPLE PCI- 88
------------------------	-----------------------	----------------

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	70 SLABS	100.00	12.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - 100.00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.

 BRANCH NAME - HANGAR APRON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A47B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 16

INSPECTION DATE - 09/06/89 PCI- 95 RATING- EXCELLENT
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

 SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 22 SLABS SAMPLE PCI- 95
 DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
 63 LINEAR CR LOW 1 SLABS 4.54 4.4
 73 SHRINKAGE CR N/A 1 SLABS 4.54 1.0

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE SEVERITY QUANTITY DENSITY-PCT DEDUCT-VALUE
 63 LINEAR CR LOW 1 SLABS 6.25 5.9
 73 SHRINKAGE CR N/A 1 SLABS 6.25 1.1

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD RELATED DISTRESSES - 84.29 PERCENT DEDUCT VALUES.
 CLIMATE/DURABILITY RELATED DISTRESSES - .00 PERCENT DEDUCT VALUES.
 OTHER RELATED DISTRESSES - 15.71 PERCENT DEDUCT VALUES.

 BRANCH NAME - HANGAR APRON SLAB LENGTH - 25.0 LF
 BRANCH NUMBER - A48B SLAB WIDTH - 25.0 LF
 SECTION NUMBER - 1 NUMBER OF SLABS - 18

INSPECTION DATE - 09/04/89 PCI- 95 RATING- EXCELLENT
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	23 SLABS	SAMPLE PCI- 95
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT
63 LINEAR CR	LOW	1 SLABS	4.34
73 SHRINKAGE CR	N/A	1 SLABS	4.34

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
63 LINEAR CR	LOW	1 SLABS	5.55	5.3
73 SHRINKAGE CR	N/A	1 SLABS	5.55	1.0

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	84.13 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	15.87 PERCENT DEDUCT VALUES.

BRANCH NAME -	WASHRACK	SLAB LENGTH -	25.0 LF
BRANCH NUMBER -	A49B	SLAB WIDTH -	25.0 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	48

INSPECTION DATE -	09/04/89	PCI-	72	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE-	24 SLABS	SAMPLE PCI- 72
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT
67 LG PATCH/UTIL	LOW	1 SLABS	4.16
63 LINEAR CR	HIGH	1 SLABS	4.16
63 LINEAR CR	MEDIUM	1 SLABS	4.16
73 SHRINKAGE CR	N/A	6 SLABS	25.00
66 SMALL PATCH	LOW	7 SLABS	29.16

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
67 LG PATCH/UTIL	LOW	2 SLABS	4.16	2.6
63 LINEAR CR	HIGH	2 SLABS	4.16	14.3
63 LINEAR CR	MEDIUM	2 SLABS	4.16	10.2
73 SHRINKAGE CR	N/A	12 SLABS	25.00	3.5
66 SMALL PATCH	LOW	14 SLABS	29.16	3.8

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	71.22 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	28.78 PERCENT DEDUCT VALUES.

BRANCH NAME -	NORTH APRON	SLAB LENGTH -	12.5 LF
BRANCH NUMBER -	A50B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	228

INSPECTION DATE -	09/01/89	PCI-	74	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	11
NUMBER OF SAMPLES SURVEYED-	2
RECOMMENDED SAMPLES TO BE SURVEYED-	7
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	6.3

SAMPLE UNIT-3 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	78
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
63 LINEAR CR	LOW	2 SLABS	10.00	8.5	
70 SCALING/CRAZING	LOW	12 SLABS	60.00	13.5	
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5	

SAMPLE UNIT-8 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	69
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
65 JT SEAL DAMAGE	MEDIUM	20 SLABS	100.00	7.0	
63 LINEAR CR	LOW	7 SLABS	35.00	18.0	
70 SCALING/CRAZING	LOW	15 SLABS	75.00	15.0	
73 SHRINKAGE CR	N/A	1 SLABS	5.00	1.0	

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	MEDIUM	228 SLABS	100.00	7.0
63 LINEAR CR	LOW	51 SLABS	22.36	14.5
70 SCALING/CRAZING	LOW	154 SLABS	67.54	14.2
73 SHRINKAGE CR	N/A	17 SLABS	7.45	1.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	39.30 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	18.97 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	41.73 PERCENT DEDUCT VALUES.

BRANCH NAME - WEST APRON
BRANCH NUMBER - A51B
SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
SLAB WIDTH - 25.0 LF
NUMBER OF SLABS - 24

INSPECTION DATE - 09/04/89 PCI- 65 RATING- GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 2
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 65

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	20 SLABS	100.00	12.0
63 LINEAR CR	LOW	6 SLABS	30.00	17.0
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	2 SLABS	10.00	1.5

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	HIGH	24 SLABS	100.00	12.0
63 LINEAR CR	LOW	7 SLABS	29.16	16.7
70 SCALING/CRAZING	LOW	24 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	2 SLABS	8.33	1.3

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	35.53 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	25.53 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	38.94 PERCENT DEDUCT VALUES.

BRANCH NAME - WEST APRON
BRANCH NUMBER - A52B
SECTION NUMBER - 1

SLAB LENGTH - 25.0 LF
SLAB WIDTH - 25.0 LF
NUMBER OF SLABS - 24

INSPECTION DATE - 09/04/89 PCI- 75 RATING- VERY GOOD
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 1
NUMBER OF SAMPLES SURVEYED- 1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 28 SLABS SAMPLE PCI- 75

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	3.57	1.3
74 JOINT SPALLING	LOW	1 SLABS	3.57	1.8
65 JT SEAL DAMAGE	HIGH	28 SLABS	100.00	12.0
63 LINEAR CR	LOW	5 SLABS	17.85	12.6
73 SHRINKAGE CR	N/A	11 SLABS	39.28	5.7
66 SMALL PATCH	LOW	1 SLABS	3.57	0.4

 EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	1 SLABS	4.16	1.5
74 JOINT SPALLING	LOW	1 SLABS	4.16	2.0
65 JT SEAL DAMAGE	HIGH	24 SLABS	100.00	12.0
63 LINEAR CR	LOW	4 SLABS	16.66	12.1
73 SHRINKAGE CR	N/A	9 SLABS	37.50	5.4
66 SMALL PATCH	LOW	1 SLABS	4.16	0.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	36.12 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	35.82 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	28.06 PERCENT DEDUCT VALUES.

BRANCH NAME -	BLDG APRON	SLAB LENGTH -	15.0 LF
BRANCH NUMBER -	A57B	SLAB WIDTH -	12.5 LF
SECTION NUMBER -	1	NUMBER OF SLABS -	160

INSPECTION DATE -	09/04/89	PCI-	79	RATING-	VERY GOOD
CONDITION-	RIDING-	SAFETY-	DRAINAGE-	SHOULDERS-	OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	18
NUMBER OF SAMPLES SURVEYED-	3
RECOMMENDED SAMPLES TO BE SURVEYED-	12
STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED-	10.7

SAMPLE UNIT-1 (RANDOM)		SAMPLE SIZE-	18 SLABS	SAMPLE PCI-	74
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	
75 CORNER SPALLING	LOW	1 SLABS	5.55	2.1	
74 JOINT SPALLING	LOW	5 SLABS	27.77	7.3	
65 JT SEAL DAMAGE	LOW	18 SLABS	100.00	2.0	
70 SCALING/CRAZING	LOW	18 SLABS	100.00	17.0	
73 SHRINKAGE CR	N/A	8 SLABS	44.44	6.4	

SAMPLE UNIT-2 (RANDOM)		SAMPLE SIZE-	20 SLABS	SAMPLE PCI-	91
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE	

65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
70 SCALING/CRAZING	LOW	4 SLABS	20.00	7.0

SAMPLE UNIT-8 (RANDOM) SAMPLE SIZE- 20 SLABS SAMPLE PCI- 71

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
65 JT SEAL DAMAGE	LOW	20 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	2 SLABS	10.00	6.0
63 LINEAR CR	LOW	2 SLABS	10.00	8.5
70 SCALING/CRAZING	LOW	20 SLABS	100.00	17.0
73 SHRINKAGE CR	N/A	7 SLABS	35.00	5.0
66 SMALL PATCH	LOW	1 SLABS	5.00	0.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	LOW	3 SLABS	1.87	0.6
74 JOINT SPALLING	LOW	14 SLABS	8.75	3.1
65 JT SEAL DAMAGE	LOW	160 SLABS	100.00	2.0
67 LG PATCH/UTIL	LOW	6 SLABS	3.75	2.3
63 LINEAR CR	LOW	6 SLABS	3.75	3.7
70 SCALING/CRAZING	LOW	116 SLABS	72.50	14.7
73 SHRINKAGE CR	N/A	41 SLABS	25.62	3.5
66 SMALL PATCH	LOW	3 SLABS	1.87	0.2

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	12.29 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	6.64 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	81.06 PERCENT DEDUCT VALUES.

BRANCH NAME -	HANGAR APRON	SECTION LENGTH -	300 LF
BRANCH NUMBER -	A59B	SECTION WIDTH -	250 LF
SECTION NUMBER -	1	SECTION AREA -	8333 SY

INSPECTION DATE - 09/03/89	PCI- 66	RATING- GOOD
CONDITION- RIDING- SAFETY-	DRAINAGE-	SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.	

SAMPLE UNIT-1 (RANDOM) SAMPLE SIZE- 5000 SF SAMPLE PCI- 66

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
47 JT REFLECT CR	MEDIUM	260 LF	5.20	28.5
48 LONG/TRANS CR	MEDIUM	200 LF	4.00	22.4

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
47 JT REFLECT CR	MEDIUM	3900 LF	5.20	28.5
48 LONG/TRANS CR	MEDIUM	3000 LF	4.00	22.4

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

INSPECTION DATE - 09/04/89 PCI- 94 RATING- EXCELLENT
CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
50 PATCHING	LOW	100 SF	2.00	5.8

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
50 PATCHING	LOW	1000 SF	1.99	5.7

LOAD	RELATED DISTRESSES	-	.00	PERCENT DEDUCT VALUES
CLIMATE/DURABILITY	RELATED DISTRESSES	-	100.00	PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES	-	.00	PERCENT DEDUCT VALUES.

A130

INSPECTION DATE - 09/04/89 PCI- 75 RATING- VERY GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 2
 NUMBER OF SAMPLES SURVEYED- 1
 RECOMMEND ALL SAMPLE UNITS TO BE SURVEYED.

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE- 5000 SF		SAMPLE PCI- 75	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
47 JT REFLECT CR	LOW	80 LF	1.60	5.2
47 JT REFLECT CR	MEDIUM	160 LF	3.20	21.3
48 LONG/TRANS CR	LOW	40 LF	0.80	4.7
48 LONG/TRANS CR	MEDIUM	80 LF	1.60	14.6

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
47 JT REFLECT CR	LOW	12000 LF	1.60	5.2
47 JT REFLECT CR	MEDIUM	24000 LF	3.20	21.3
48 LONG/TRANS CR	LOW	6000 LF	0.80	4.7
48 LONG/TRANS CR	MEDIUM	12000 LF	1.60	14.6

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	100.00 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	.00 PERCENT DEDUCT VALUES.

BRANCH NAME - HANGAR APRON	SLAB LENGTH - 25.0 LF
BRANCH NUMBER - A63B	SLAB WIDTH - 25.0 LF
SECTION NUMBER - 1	NUMBER OF SLABS - 128

INSPECTION DATE - 09/01/89 PCI- 60 RATING- GOOD
 CONDITION- RIDING- SAFETY- DRAINAGE- SHOULDERS- OVERALL-

TOTAL NUMBER OF SAMPLES IN SECTION- 6
 NUMBER OF SAMPLES SURVEYED- 2
 RECOMMENDED SAMPLES TO BE SURVEYED- 6
 STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED- 18.3

SAMPLE UNIT-1 (RANDOM)	SAMPLE SIZE- 30 SLABS		SAMPLE PCI- 73	
DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 COPNER SPALLING	HIGH	2 SLABS	6.66	6.4
75 CORNER SPALLING	LOW	1 SLABS	3.33	1.2
74 JOINT SPALLING	LOW	2 SLABS	6.66	2.6
74 JOINT SPALLING	MEDIUM	3 SLABS	10.00	8.0

65 JT SEAL DAMAGE	HIGH	30 SLABS	100.00	12.0
73 SHRINKAGE CR	N/A	7 SLABS	23.33	3.2
66 SMALL PATCH	MEDIUM	3 SLABS	10.00	5.5

SAMPLE UNIT-6 (RANDOM)	SAMPLE SIZE-	18 SLABS	SAMPLE PCI-	47
------------------------	--------------	----------	-------------	----

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
74 JOINT SPALLING	HIGH	1 SLABS	5.55	14.2
74 JOINT SPALLING	MEDIUM	1 SLABS	5.55	4.8
65 JT SEAL DAMAGE	HIGH	18 SLABS	100.00	12.0
63 LINEAR CR	LOW	2 SLABS	11.11	9.1
63 LINEAR CR	MEDIUM	4 SLABS	22.22	29.7
73 SHRINKAGE CR	N/A	2 SLABS	11.11	1.6
66 SMALL PATCH	LOW	1 SLABS	5.55	0.7
66 SMALL PATCH	MEDIUM	2 SLABS	11.11	5.9

EXTRAPOLATED DISTRESS QUANTITIES FOR SECTION-

DISTRESS TYPE	SEVERITY	QUANTITY	DENSITY-PCT	DEDUCT-VALUE
75 CORNER SPALLING	HIGH	5 SLABS	3.90	4.1
75 CORNER SPALLING	LOW	3 SLABS	2.34	0.8
74 JOINT SPALLING	HIGH	3 SLABS	2.34	7.3
74 JOINT SPALLING	LOW	5 SLABS	3.90	1.9
74 JOINT SPALLING	MEDIUM	11 SLABS	8.59	7.1
65 JT SEAL DAMAGE	HIGH	128 SLABS	100.00	12.0
63 LINEAR CR	LOW	5 SLABS	3.90	3.9
63 LINEAR CR	MEDIUM	11 SLABS	8.59	17.2
73 SHRINKAGE CR	N/A	24 SLABS	18.75	2.6
66 SMALL PATCH	LOW	3 SLABS	2.34	0.3
66 SMALL PATCH	MEDIUM	13 SLABS	10.15	5.5

*** PERCENT OF DEDUCT VALUES BASED ON DISTRESS MECHANISM ***

LOAD	RELATED DISTRESSES -	33.65 PERCENT DEDUCT VALUES.
CLIMATE/DURABILITY	RELATED DISTRESSES -	19.14 PERCENT DEDUCT VALUES.
OTHER	RELATED DISTRESSES -	47.21 PERCENT DEDUCT VALUES.

BRANCH NAME - POWER TRIM PAD	SECTION LENGTH - 153 LF
BRANCH NUMBER - A64B	SECTION WIDTH - 85 LF
SECTION NUMBER - 1	SECTION AREA - 1477 SY

INSPECTION DATE - 09/04/89	PCI- 81	RATING- VERY GOOD
----------------------------	---------	-------------------

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS BE SURVEYED.	

BRANCH NAME - POWER TRIM PAD	SECTION LENGTH - 250 LF
BRANCH NUMBER - A65B	SECTION LENGTH - 60 LF
SECTION NUMBER - 1	SECTION AREA - 1667 SY

INSPECTION DATE - 09/04/89	PCI- 65	RATING- GOOD
----------------------------	---------	--------------

TOTAL NUMBER OF SAMPLES IN SECTION-	7
NUMBER OF SAMPLES SURVEYED-	1
RECOMMENDED NUMBER OF SAMPLE UNITS TO BE SURVEYED-	5

BRANCH NAME - APRON	SECTION LENGTH - 204 LF
BRANCH NUMBER - A66B	SECTION WIDTH - 51 LF
SECTION NUMBER - 1	SECTION AREA - 1156 SY

INSPECTION DATE - 09/04/89	PCI- 96	RATING- EXCELLENT
----------------------------	---------	-------------------

TOTAL NUMBER OF SAMPLES IN SECTION-	2
NUMBER OF SAMPLES SURVEYED-	1
RECOMMEND ALL SAMPLE UNITS BE SURVEYED.	

